

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	22 BR	MC LEAN	28	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

				80% FED 20% STATE		
				ROADWAY	SN 057-0076	SFTY-3N
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QNTY	X080-2A	X080-2A	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	0	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	0	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	13	13	0	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	0	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	378	378	0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	101	101	0	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	375	375	0	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	350	350	0	
△ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1510	1510	0	
△ 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	189	189	0	
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6	0	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	0	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	0	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	541	541	0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6	0	
X0321743	SILICONE JOINT SEALER, 1"	FOOT	47	0	47	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	131	117	14	
△ Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22	0	22	
Z0002600	BAR SPLICERS	EACH	6	0	6	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	0	0	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	0	0	2

△ SPECIALTY ITEMS

PLOT DATE = 12/15/2008
 FILE NAME = ..\v8\summary of quantities.dgn
 PLOT SCALE = 800000 / 1 IN.
 USER NAME = CFC

COOMBE-BLOXDORF P.C.
 Engineers / Land Surveyors
 Springfield, Illinois
 Design Firm License No. 184-002703

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 IL ROUTE 9 OVER MONEY CREEK
 FAP RT 693, SECTION 22 BR
 MC LEAN COUNTY
 SCALE: DATE
 DRAWN BY CFC / TFG
 CHECKED BY MCB