

NOTES:

 The contractor has the option of either method A or B for a Downward Adjustment. Shop Shop Drawings for the Precisit Concrete Top shoil be submitted to the engineer for his approval prior to the delivery of the Top to the job site. Lowering may also be accomplished by removing existing adjusting rings or brick masonry.

3. This work shall be done in accordance with details herein shown and Section 602 of the Standard Specifications.

4. This work shall be paid for atthe contract unit price each for "Manholes to be Adjusted Special" and no additional compensation shall be allowed.

MANHOLE ADJUSTMENT DETAIL

