F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6998	99-00209-02-PV	VERMILION	72	17
STA. 103+00	TO STA. 109+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT-		
		CONTRACT NO.: 91356		

PLAN
SURVEYED
DRAWN
ALIGNMENT CHECKED
PLANS PREPARED
CADD FILE NAME
NOTE BOOK
NO.
BY
DATE

ENTRANCE QUANTITY SCHEDULE

TYPE	STATION	LT/RT	AGG SURF CSE B (TONS)	TEMP ACCESS-PRIV ENT (EACH)
P.E.	105+50.41	LT	24.0	1
SHEET TOTALS			24.0	1

GUARDRAIL SCHEDULE

FROM STATION	TO STATION	LT/RT	TRAF BAR TERM T6 (EACH)	SPBGR TY A (FT)	GUARDRAIL MARKERS (EACH)
106+85.70	107+18.85	LT	1		
107+18.85	109+00.00	LT		181.15	3
SHEET TOTALS			1	181.15	3

(P1) TO (P4) = REFERENCE PROPOSED TYPICAL SECTIONS

SW 1/4 SEC. 28 T20N-R11W 2nd P.M.

SEE ENTRANCE DETAILS FOR ENTRANCE DIMENSIONS

N

0 20 40

1" = 20'

℄ EXISTING WEST TRACK

℄ EXISTING EAST TRACK

5526

26

PROP. T.E.

EXIST. R.O.W.

TREES & BRUSH

BEGIN INTERIM PAVEMENT STA. 104+52.66

PR. FUTURE ℄ WINTER AVE.

24" SAN. S.

STA. 104+11.39 BEGIN PR. ℄ INTERIM PAVEMENT

5527

CSX

27

104+52.66

2' AGG. SHDR.

SECTION LINE

103 104 105+00 106 107 108

WINTER AVE

O&C

MATCHLINE 109+00 (WINTER AVENUE)

P1 P2 P3 P4

105+51.20

105+81.20

106+88.20

107+18.20

108+76.02

P.E. 105+50.41

12" W

AGG

GATE POST

24" SAN. S.

TREES & BRUSH

P CUL CL A 2 24 - 54 FT
U.S.F.L.: STA. 105+27.75
O/S 38.44' LT. EL. 611.00
D.S.F.L.: STA. 105+81.73
O/S 37.00' LT. EL. 609.35
W/ PRC FLAR END SEC 24 - 2 EACH

24" RCCP

BEGIN STONEY CREEK BRIDGE STA. 105+81.20

END STONEY CREEK BRIDGE STA. 106+88.20

STONEY CREEK

PR. TBT TY. 6

PR. SPBGR TY. A

PR. SHEET PILING (SEE BRIDGE PLANS)

SHEET PILES

PROP. R.O.W.

CONST. LIMITS

203 204 205+00 206 207

PR. ℄ INTERIM PAVEMENT

OFP

24"

30' BRIDGE APPROACH PAVEMENT (SPECIAL) (SEE DETAIL SHEET)

STA. 205+61.98

STA. 207+07.94

5528

28

RR

5529

29

PROP. R.O.W.

RET. WALL

PR. FUTURE ℄ BICYCLE PATH

EXIST. R.O.W.

PROP. T.E.

TREES & BRUSH

EX. RIPRAP

CONST. LIMITS

PR. AGGREGATE DITCH (SEE DITCH LINING SCHEDULE)

PR. FIBER MAT (SEE DITCH LINING SCHEDULE)

END INTERIM PAVEMENT STA. 108+76.02

MATCHLINE 209+00 (BICYCLE PATH)

NW 1/4 SEC. 33 T20N-R11W 2nd P.M.

DITCH CONTROL

① STA. 106+73.4, 82.3' RT.
② STA. 106+82.2, 77.3' RT.
③ STA. 107+03.6, 62.2' RT.
④ STA. 107+22.0, 55.6' RT.
⑤ STA. 107+27.1, 74.0' RT.
⑥ STA. 107+50.00, 46.3' RT.
⑦ STA. 107+75.00, 41.2' RT.
⑧ STA. 108+00.00, 42.0' RT.
⑨ STA. 108+50.00, 42.0' RT.

PORTLAND CEMENT CONCRETE SIDEWALK 9" SPECIAL SCHEDULE

FROM STATION	TO STATION	PC CONC SIDEWALK 9" SP (SF)
205+61.98	205+80.90	296.0
206+87.90	207+07.94	313.0
SHEET TOTALS		609.0

BRIDGE APPROACH PAVEMENT (SPECIAL)

FROM STATION	TO STATION	BRIDGE APPR PAVT SPL (SY)	PROTECTIVE COAT (SY)
105+51.20	105+81.20	104.7	107.2
106+88.20	107+18.20	103.9	107.2
SHEET TOTALS		208.6	214.4

REVISIONS NAME	DATE

CITY OF DANVILLE, ILLINOIS

WINTER AVENUE RECONSTRUCTION
PROPOSED ROADWAY PLAN
WINTER AVENUE/BICYCLE PATH
STA. 103+00 TO STA. 109+00

SCALE: 1" = 20' DATE: 12/30/05

DRAWN BY: NIL CHECKED BY: XXX