

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	10(B-1, BR-2)	MONTGOMERY	104	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUBBASE GRANULAR MATERIAL, TYPE A 12"						
STA	TO	STA	LENGTH (FT)	WIDTH (FT)	DEPTH (")	AREA (SQ YD)
10+43.22		12+00.00	156.78	20	12	348.4
12+00.00		12+75.00	75.00	20 to 12 (AVG. =16)	12	133.3
12+75.00		13+50.00	75.00	12	12	100.0
TOTAL =						581.7 SQ YD

SUBBASE GRANULAR MATERIAL, TYPE A 4"							
STA	TO	STA	LENGTH (FT)	OFFSET	WIDTH (FT)	DEPTH (")	AREA (SQ YD)
IL 185							
488+53.00		492+48.15	395.15	LT	4	4	175.6
492+93.88		493+80.00	86.12	LT	4	4	38.3
494+50.00		499+37.00	487.00	LT	6	4	324.7
501+24.68		501+54.68	30.00	LT	6 AVG	4	20.0
501+54.68		504+40.00	285.32	LT	8	4	253.6
504+40.00		505+00.00	60.00	LT	6 AVG	4	40.0
505+00.00		509+35.00	435.00	LT	4	4	193.3
509+35.00		509+71.00	36.00	LT	2.5 AVG	4	10.0
488+74.00		492+48.15	374.15	RT	4	4	166.3
492+93.88		499+35.00	641.12	RT	6	4	427.4
501+09.60		508+70.00	760.40	RT	8	4	675.9
TR 318							
10+12.00		10+43.22	31.22	UNDER PVMT	VARIES	4	112.0
TOTAL =							2437.1 SQ YD

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 777 (IL RTE. 185)
 SECTION 10(B-1, BR-2)
 MONTGOMERY COUNTY

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____

PLOT DATE = 1/23/2006
 FILE NAME = s:\projects\92667\shwsodgn
 PLOT SCALE = 50.0000 / IN
 USER NAME = sleggett