

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	10(B-1, BR-2)	MONTGOMERY	104	162
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS FED. AID PROJECT		

BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE, IL-19.0, N50

STATION	TO	STATION	OFFSET	LENGTH (FT)	T (FT)*	PAY WIDTH (FT)	TONS
IL 185 WEST OF SHOAL CREEK							
497+13.50		497+50.00	LT Lane	36.5	0.11	12.0	3.4
497+50.00		497+75.00	LT Lane	25.0	0.31	12.2	7.1
497+75.00		498+00.00	LT Lane	25.0	0.51	12.4	11.8
498+00.00		498+25.00	LT Lane	25.0	0.68	12.7	16.1
498+25.00		498+50.00	LT Lane	25.0	0.82	13.1	19.9
498+50.00		498+75.00	LT Lane	25.0	0.94	13.4	23.5
498+75.00		499+00.00	LT Lane	25.0	1.05	13.8	26.9
499+00.00		499+25.00	LT Lane	25.0	1.13	14.2	30.0
499+25.00		499+35.49	LT Lane	10.5	1.18	14.6	13.4
IL 185 EAST OF SHOAL CREEK							
501+52.54		502+00.00	LT Lane	47.5	1.78	13.9	87.5
502+00.00		502+50.00	LT Lane	50.0	1.93	14.3	103.0
502+50.00		503+00.00	LT Lane	50.0	2.00	14.6	109.0
503+00.00		503+50.00	LT Lane	50.0	1.88	14.6	102.6
503+50.00		504+00.00	LT Lane	50.0	1.41	14.2	74.8
504+00.00		504+50.00	LT Lane	50.0	0.80	13.6	40.5
504+50.00		505+00.00	LT Lane	50.0	0.34	13.0	16.3
505+00.00		505+47.75	LT Lane	47.8	0.04	12.8	1.6
IL 185 WEST OF SHOAL CREEK							
497+13.50		497+50.00	RT Lane	36.5	0.11	14.4	4.1
497+50.00		497+75.00	RT Lane	25.0	0.31	14.4	8.3
497+75.00		498+00.00	RT Lane	25.0	0.51	14.4	13.7
498+00.00		498+25.00	RT Lane	25.0	0.68	14.3	18.2
498+25.00		498+50.00	RT Lane	25.0	0.82	14.2	21.6
498+50.00		498+75.00	RT Lane	25.0	0.94	14.1	24.6
498+75.00		499+00.00	RT Lane	25.0	1.05	13.9	27.2
499+00.00		499+25.00	RT Lane	25.0	1.13	13.7	29.0
499+25.00		499+35.49	RT Lane	10.5	1.18	13.6	12.5

* = AVERAGE THICKNESS

CONTINUE BINDER COURSE SCHEDULE ON NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 777 (IL RTE. 185)
 SECTION 10(B-1, BR-2)
 MONTGOMERY COUNTY
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____