

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	10(B-1, BR-2)	MONTGOMERY	104	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

BITUMINOUS BASE COURSE SUPERPAVE 10"

STA	TO	STA	LENGTH (FT)	OFFSET	WIDTH (FT)	DEPTH (")	AREA (SQ YD)
IL 185							
488+53.00		492+48.15	395.15	LT	4.83	10	212.1
492+93.88		493+80.00	86.12	LT	4.83	10	46.2
494+50.00		499+37.00	487.00	LT	6.83	10	369.6
501+24.68		501+54.68	30.00	LT	6.83 AVG	10	22.8
501+54.68		504+40.00	285.32	LT	8.83	10	279.9
504+40.00		505+00.00	60.00	LT	6.83 AVG	10	45.5
505+00.00		509+35.00	435.00	LT	4.83	10	233.5
509+35.00		509+71.00	36.00	LT	3.33 AVG	10	13.2
488+74.00		492+48.15	374.15	RT	4.83	10	200.8
492+93.88		499+35.00	641.12	RT	6.83	10	486.5
501+09.60		508+70.00	760.40	RT	8.83	10	746.0
TOTAL =							2745.3 SQ YD

BITUMINOUS BASE COURSE SUPERPAVE 8"

STA	TO	STA	AREA (SQ FT)	OFFSET	WIDTH (FT)	DEPTH (")	AREA (SQ YD)
IL 318							
10+12.00		10+43.22	1008	N/A	VARIES	8	112.0
TOTAL =							112.0 SQ YD

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAP 777 (IL RTE. 185)  
 SECTION 10(B-1, BR-2)  
 MONTGOMERY COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

PLOT DATE = 1/23/2006  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = aleglent