

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	G24B/B-1	FAYETTE	22	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X028-2A		
20200100	EARTH EXCAVATION	CU YD	497	497		
20201500	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	252	252		
20900110	POROUS GRANULAR BACKFILL	CU YD	280	280		
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2	0.2		
25100115	MULCH, METHOD 2	ACRE	0.1	0.1		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10		
28000300	TEMPORARY DITCH CHECKS	EACH	4	4		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1075	1075		
28200200	FILTER FABRIC	SQ YD	1075	1075		
35650700	BASE COURSE WIDENING	SQ YD	325	325		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	48	48		
40600300	AGGREGATE (PRIME COAT)	TON	1.9	1.9		
44000100	PAVEMENT REMOVAL	SQ YD	255	255		
44004250	PAVED SHOULDER REMOVAL	SQ YD	622	622		
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	43	43		
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	276	276		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
50800105	REINFORCEMENT BARS	POUND	47840	47840		
51205200	TEMPORARY SHEET PILING	SQ FT	650	650		
51500100	NAME PLATES	EACH	1	1		
54003000	CONCRETE BOX CULVERTS	CU YD	180.6	180.6		
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	526	526		
*63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	87.5	87.5		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	68	68		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1538	1538		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X028-2A		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	23	23		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	350	350		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	350	350		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1568	1568		
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	1504	1504		
X0348700	AGGREGATE DITCH CHECK	EACH	1	1		
X3560172	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 13 3/4 INCH	SQ YD	47	47		
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	1	1		
X4073155	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 3/4"	SQ YD	321	321		
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	4	4		
Z0002600	BAR SPLICERS	EACH	118	118		
Δ Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2		
Δ Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2		

Δ SFTY-34
*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
HORIZ.

DRAWN BY
CHECKED BY

Rev.

teasleyck
12/22/2005
:\projects\94778\d04899pa.dgn

PLOT DATE = 12/22/2005
FILE NAME = c:\projects\94778\d04899pa.dgn
USER NAME = teasleyck