

PROJECT NO.	SECTION	COUNTY	SHEET NO.	TOTAL SHEETS
9397	01-00022-00-RP	MADISON	72	6
STA.		TO STA.		

CONTRACT NO. 97269

CURB, GUTTER & SIDEWALK SCHEDULE

STATION	TO	STATION	GUTTER REMOVAL	COMB. CONC. CURB & GUTTER REMOVAL	SIDEWALK REMOVAL	COMB. CONC. CURB & GUTTER TYPE B6.24	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	DETECTABLE WARNINGS
			FEET	FEET	SQ FT	FEET	SQ FT	SQ FT
LOWER MARINE ROAD								
10+19.00	LT	TO	10+36.00	LT	154.00			
10+19.00	RT	TO	10+31.00	RT	102.50			
10+19.00	LT	TO	10+44.00	LT			153.50	20.00
10+19.00	RT	TO	10+44.00	RT			346.50	34.00
10+19.05	LT	TO	10+49.55	LT		44.53		
10+19.05	RT	TO	10+49.55	RT		44.53		
10+20.38	LT	TO	10+35.98	LT				
10+35.98	LT	TO	13+05.84	LT	294.46	34.68		
10+36.00	LT	TO	11+46.09	LT				
10+44.00	LT	TO	11+46.09	LT			550.45	
10+44.00	RT	TO	15+70.56	RT			510.45	
10+49.55	LT	TO	36+25.00	LT			5,265.60	
10+49.55	RT	TO	36+25.00	RT		2,390.45		
11+11.08	LT	TO	TIE-IN					
11+58.09	LT	TO	12+14.68	LT			7.96	7.96
11+84.90	LT	TO	TIE-IN					282.95
12+26.68	LT	TO	12+98.00	LT			6.92	6.92
12+26.68	LT	TO	12+51.51	LT				356.60
12+71.51	LT	TO	12+82.51	LT				124.15
12+82.51	LT	TO	12+96.51	LT				55.00
12+98.00	LT	TO	13+04.00	LT				218.50
12+95.00	RT	TO	RAMP					36.00
12+98.00	RT	TO	15+70.56	RT			75.00	10.00
13+32.50	RT	TO	TIE-IN					1362.80
13+51.62	LT	TO	18+76.17	LT	591.32			464.00
13+57.00	LT	TO	14+17.26	LT				368.00
13+59.96	RT	TO	18+47.62	RT		495.92		
13+61.00	RT	TO	RAMP					
13+61.50	LT	TO	13+73.50	LT			75.00	10.00
13+73.50	LT	TO	14+17.26	LT			48.00	14.00
14+01.16	LT	TO	TIE-IN					218.80
14+29.26	LT	TO	14+45.79	LT			4.21	4.21
14+57.79	LT	TO	15+07.66	LT			66.12	82.65
15+19.66	LT	TO	15+78.49	LT			199.48	249.35
15+94.49	LT	TO	17+56.31	LT			235.32	294.15
16+04.56	RT	TO	19+22.00	RT			647.28	809.10
16+04.56	RT	TO	20+39.93	RT			1587.20	
16+12.43	LT	TO	TIE-IN					4,353.70
17+24.72	LT	TO	TIE-IN					4.30
17+47.00	RT	TO	TIE-IN					11.54
17+56.31	LT	TO	18+59.00	LT				455.50
17+72.31	LT	TO	18+58.77	LT				377.00
18+43.00	RT	TO	TIE-IN					475.00
18+47.62	RT	TO	19+21.85	RT	90.77			312.00
18+79.77	LT	TO	18+99.97	LT				101.00
18+80.00	LT	TO	18+85.00	LT				116.00
19+11.97	LT	TO	20+41.10	LT				645.65
19+22.00	RT	TO	20.39.93	RT				471.72
20+56.10	LT	TO	22+02.00	LT				729.50
20+63.93	RT	TO	21+89.47	RT				1,255.40
20+73.93	RT	TO	21+89.47	RT				462.16
21+89.47	RT	TO	24+85.73	RT				1,777.56
22+22.00	LT	TO	22+91.53	LT				347.65
23+15.33	LT	TO	23+46.60	LT				155.35
23+59.60	LT	TO	25+89.95	LT				1,151.75
24+85.73	RT	TO	26+51.38	RT				1,656.50
26+04.95	LT	TO	26+52.78	LT				239.15
26+67.78	LT	TO	27+86.56	LT				593.90
26+73.38	RT	TO	27+73.00	RT				
26+73.38	RT	TO	27+51.00	RT		398.48		
27+51.00	RT	TO	27+67.00	RT				776.20
28+02.56	LT	TO	29+84.03	LT				121.00
28+16.00	RT	TO	28+36.00	RT				907.35
28+20.00	RT	TO	31+19.00	RT				143.00
28+36.00	RT	TO	30+94.00	RT				2,580.00
30+08.03	LT	TO	30+93.00	LT				424.85
30+93.00	LT	TO	31+08.00	LT				63.00
30+94.00	RT	TO	31+09.00	RT				115.50
31+48.00	RT	TO	31+63.00	RT				63.00
31+57.00	RT	TO	33+03.28	RT				63.00
31+57.00	LT	TO	31+72.00	LT		582.12		20.00
31+72.00	LT	TO	33+30.39	LT				791.95
33+42.39	LT	TO	34+95.30	LT				764.55
35+12.30	LT	TO	35+35.95	LT				118.25
CLAY STREET								
10+13	TO	10+43				87.9		
10+43	RT	TO	10+49	RT	6.00			
10+43	LT	TO	10+49	LT	6.00			
JAMES DRIVE								
10+13	TO	10+63				137.31		
BASS DRIVE								
10+13	TO	10+69.82				141.33		
10+69.82	RT	TO	10+75.82	RT	6.00			
10+69.82	LT	TO	10+75.82	LT	6.00			
KENNETH DRIVE								
9+87	TO	9+30.22				232.70		
TOTAL			1,000.55	530.60	11,744.75	5,464.20	30,314.39	270.00

MISCELLANEOUS DRAINAGE ITEMS

STATION	MANHOLES TO BE ADJ.	PLUG EXIST. CULVERTS	REMOVE EXIST INLETS
	(EACH)	(EACH)	(EACH)
LOWER MARINE RD.			
13+28.44	1		
16+30.23	1		
18+71.48			1
18+74.65	1		
18+90.20		1	
20+11.60	1		
21+26.30	1		
22+31.64	1		
24+12.66	1		
28+10.36	1		
31+36.59			1
KENNETH DR.			
5+34.24		1	
5+36.15			1
TOTAL			
	8	2	3

REVISIONS	
NAME	DATE

SCHEDULES

LOWER MARINE ROAD IMPROVEMENTS
CITY OF TROY
MADISON COUNTY, ILLINOIS

P:\000139A\dwg\000139ASCHED.dwg 12/9/2005 10:55:08 AM CST