

FILE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8397	01-00022-00-RP	MADISON	72	9
STA.		TO STA.		

CONTRACT NO. 97269

LOWER MARINE ROAD										
STATION	TO	STATION	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SUB-BASE GRANULAR MATL., TYPE-A 4"	PROCESSING LIME MODIFIED SOIL 12"	LIME	AGGREGATE BASE CSE., TYPE-A, 8"	AGGREGATE (PRIME COAT)	BIT. MATERIALS (PRIME COAT)	INCIDENTAL BIT. SURFACING, SUPERPAVE, N70
			SQ YD	SQ YD	SQ YD	TON	SQ YD	TON	TON	TON
10+19.05	TO	10+49.55	131.05	156.58	161.53	3.11				
10+49.55	TO	36+25.00	7,440.19	8,809.28	9,074.61	174.78				
36+25.00	TO	36+75.01					131.5	0.33	0.21	22.10
SUB TOTAL			7,571	8,966	9,236	178	131.5	0.33	0.21	22.1

JAMES DRIVE										
STATION	TO	STATION	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SUB-BASE GRANULAR MATERIAL TYPE-A, 4"	PROCESSING MODIFIED SOILS-12"	LIME	AGGREGATE BASE CSE. TYPE-A, 8"	AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	INCIDENTAL BIT. SURFACING, SUPERPAVE N 70
			SQ YD	SQ YD	SQ YD	TON	SQ YD	TON	TON	TON
10+13	TO	10+88	228	267	275.00	6	60.47	0.15	0.10	10.16
SUB TOTAL			228	267	275	6	60.5	0.15	0.10	10.16

CLAY STREET										
STATION	TO	STATION	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SUB-BASE GRANULAR MATERIAL TYPE-A, 4"	PROCESSING MODIFIED SOILS-12"	LIME	AGGREGATE BASE CSE. TYPE-A, 8"	AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	INCIDENTAL BIT. SURFACING, SUPERPAVE N 70
			SQ YD	SQ YD	SQ YD	TON	SQ YD	TON	TON	TON
10+13	TO	10+49	190	216	220.00	4	29.5	0.07	0.05	4.96
SUB TOTAL			190	216	220	4	29.5	0.07	0.05	4.96

BASS DRIVE & KENNETH DRIVE										
STATION	TO	STATION	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SUB-BASE GRANULAR MATERIAL, TYPE-A, 4"	PROC. MOD. SOILS 12"	LIME	AGGREGATE BASE CSE. TYPE-A, 8"	AGGREGATE (PRIME COAT)	BITUMINOUS MATLS. (PRIME COAT)	INCIDENTAL BIT. SURFACING, SUPERPAVE, N70
			SQ YD	SQ YD	SQ YD	TON	SQ YD	TON	TON	TON
BASS DRIVE										
10+13	TO	10+75.82	212	253	260.00	5	17.5	0.04	0.03	2.93
KENNETH DRIVE										
9+10.22	TO	9+87.00	344	411	424.00	8	68.8	0.17	0.11	11.56
SUB TOTAL			556	664	684	13	86.3	0.21	0.14	14.49

TOTAL PAVING QUANTITIES										
ROADWAY	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SUB-BASE GRANULAR MATL., TYPE-A 4"	PROCESSING LIME MODIFIED SOIL 12"	LIME	AGGREGATE BASE CSE., TYPE-A, 8"	AGGREGATE (PRIME COAT)	BIT. MATERIALS (PRIME COAT)	INCIDENTAL BIT. SURFACING, SUPERPAVE, N70		
	SQ YD	SQ YD	SQ YD	TON	SQ YD	TON	TON	TON		
LOWER MARINE ROAD	7,571.00	8,966.00	9,236.00	178	131.5	0.33	0.21	22.10		
JAMES DRIVE	228.00	267.00	275.00	6	60.5	0.15	0.10	10.16		
CLAY STREET	190.00	216.00	220.00	4	29.5	0.07	0.05	4.96		
BASS DRIVE AND KENNETH DRIVE	556.00	664.00	684.00	13	86.3	0.21	0.14	14.49		
GRAND TOTAL	8,545	10,113	10,415	201	307.8	0.33	0.50	51.7		

REVISIONS	
NAME	DATE

SCHEDULES

LOWER MARINE ROAD IMPROVEMENTS
CITY OF TROY
MADISON COUNTY, ILLINOIS

P:\000139A\dwg\000139A\SCHED.dwg 12/9/2005 10:55:08 AM CST