



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 24, 2006

SUBJECT: Park & Ride Facility
Project CMM-5011(215)
Section 00-00012-00-PK
Madison County
Contract No. 97270
Item 45
March 10, 2006 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Plans – Sheet 3, deleted pay item 44000030 “Bituminous Surface Removal (Variable Depth).

Proposal – Page 2 of Schedule of Prices, deleted pay item 44000030, removed special provision for “Bituminous Surface Removal (Variable Depth).

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are displayed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Michael L. Hine
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "DE" monogram.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

INDEX TO SPECIAL PROVISIONS

<u>SPECIAL PROVISION</u>	<u>SHEET</u>
DESCRIPTION OF WORK.....	1
SITE INSPECTION.....	1
PROJECT FEES.....	1
TRAFFIC CONTROL PLAN.....	1
TRAFFIC CONTROL AND PROTECTION	2
CONSTRUCTION AND MAINTENANCE SIGN SUPPORTS.....	3
SIGN REMOVAL AND REPLACEMENT.....	4
BARRICADES OR DRUMS	4
JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (J.U.L.I.E.)	5
PROTECTION OF EXISTING STRUCTURES	5
THOROUGHFARE PROTECTION AND SAFETY.....	5
PUBLIC PROTECTION	5
EQUIPMENT SITTING/STORAGE.....	6
PASSENGER SHELTER REMOVAL.....	6
SIGN REMOVAL	6
OIL AND CHIP REMOVAL.....	6
AGGREGATE SHOULDERS, TYPE A	6
<i>Removed - 2-24-06</i>	
RIP RAP REMOVAL.....	7
WHEEL STOP REMOVAL AND REPLACEMENT.....	7
PCC PAVEMENT EXPANSION JOINT CAPS	7
CONCRETE SURFACE CURING AND SEALING	8
CONCRETE EXPANSION AND CONTROL JOINTS, 5" CONCRETE SIDEWALK.....	8
TEMPORARY CONSTRUCTION EXIT PAD	8
FURNISH AND INSTALLING CONCRETE WHEEL STOPS.....	9
WATER SERVICE AND GROUND HYDRANT.....	9
6" DIAMETER PIPE BOLLARD, CONCRETE FILLED.....	9
PASSENGER SHELTER.....	9
OUTDOOR LIGHTING IMPROVEMENTS.....	32
STATUS OF UTILITIES TO BE ADJUSTED.....	40
SEEDING, CLASS 1.....	41
ACCESSIBLE PARKING SIGN.....	41
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	42

This item of work shall consist of furnishing all labor, equipment and materials necessary to provide 2 foot wide aggregate shoulder, 3 inches thick around the perimeter of the bituminous surface. Shoulder to be constructed with 4% slope toward perimeter ditch or detention basin.

Payment for this work shall be made at the contract unit price per ton for AGGREGATE SHOULDERS, TYPE A and no additional compensation will be allowed.

2-24-06 Removed Special Provision for
Bituminous Surface Removal
(Variable Depth)

RIP RAP REMOVAL

This item of work shall consist of furnishing all labor, equipment and materials necessary to remove and replace existing rip rap, including all granular bedding at locations shown in the plans.

Payment for this work shall be included in the cost of EARTH EXCAVATION.

WHEEL STOP REMOVAL AND REPLACEMENT

This item of work shall consist of furnishing all labor, equipment and materials necessary to remove existing wheel stops located within the existing park-ride facility, stockpile, and relocate to locations defined in the plans as directed by the Engineer upon completion of the proposed parking lot improvements.

Payment for this work shall be made at the contract unit price per each for WHEEL STOP REMOVAL AND REPLACEMENT and no additional compensation will be allowed.

PCC PAVEMENT EXPANSION JOINT CAPS

The PCC pavement expansion joints shall be constructed according to Section 420 of the Standard Specifications and to the requirements of Highway Standard 420001 except that the dowel expansion cap as detailed under the "EXPANSION JOINT" drawing, found on sheet 2 of 2 of the standard drawings, shall be made of plastic and shall have a minimum length of 4". All caps shall meet the approval of the Engineer. Metal caps shall not be permitted.

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
25000100	SEEDING CL 1	ACRE	1.500 X		=		
25100630	EROSION CONTR BLANKET	SQ YD	157.000 X		=		
28000300	TEMP DITCH CHECKS	EACH	6.000 X		=		
28000400	PERIMETER EROS BAR	FOOT	1,103.000 X		=		
28000500	INLET & PIPE PROTECT	EACH	3.000 X		=		
28100707	STONE DUMP RIP CL A4	SQ YD	6.000 X		=		
28200200	FILTER FABRIC	SQ YD	6.000 X		=		
30200850	PROCESS MOD SOIL 16	SQ YD	6,615.000 X		=		
30201500	LIME	TON	219.000 X		=		
35100100	AGG BASE CSE A	TON	625.000 X		=		
35100700	AGG BASE CSE A 8	SQ YD	6,804.000 X		=		
40600100	BIT MATLS PR CT	GALLON	2,516.000 X		=		
42000201	PCC PVT 7 JOINTED	SQ YD	1,515.000 X		=		
42400200	PC CONC SIDEWALK 5	SQ FT	1,224.000 X		=		

2-24-06 Deleted Pay Item 44000030