

INTERCEPTOR NO. 9 STRUCTURE DEMOLITION - PLANS AND SECTIONS

## OFFICE OF WATER RESOURCES

Field verify all existing dimensions, elevations and conditions in the field prior to start of construction. Dimensions indicated are approximate and for reference only. No additional payment will be made as a result of differing dimensions or elevations

2. Remove portion of existing MWRDGC structure as shown. Protect portion of existing structure to remain. Removal shall be in accordance with Section 501 of the Standard Specifications except separate payment will not be made for this Work. Cost is included in the Interceptor No. 9 Structure lump sum.

3. Where existing sewer pipes have been plugged, the Contractor shall not disturb the existing plugs. Where these plugs do not interfere with the alignment of the new 12" Storm Sewer. Where interference occurs, the Contractor must remove pipe flush with wall and plug openings watertight. No extra payment will be made for this work Any leakage observed must be repaired watertight by the Contractor.

4. Prior to start of demolition and excavation on the north side of the structure, the Contractor shall remove earth fill evenly from both the north and south sides of the structure, and maintain excavation dewatering so work can be completed in the dry. Earth shall be removed to approximate Elevation 620.00 on the south side of the existing structure to prevent imposing unbalanced forces on the existing structure, including overturning and sliding.

5. The Contractor must provide a temporary soil retention system to protect the existing adjacent roadway, existing utilities and structures. The Contractor must provide additional temporary earth retention systems, whether or not shown on the drawings, as required for this protection. Refer to the GENERAL NOTES on Drawing SGN-1. This work will not be measured for payment but is included in the interceptor No. 9 structure lump sum pay item.

6. Backfill evenly both sides of structure to prevent imposing unbalanced lateral soil loads on the existing structure.

7. Field verify location and elevation of existing pipe prior to driving steel sheeting for the new sheet pile flood wall.

8. The actual orientation of the Junction Structure to the Drop Structure is unknown and must be measured in the field prior to fabrication of the isolation gate that is to be inserted between these two structures. Thus, an exploratory dig will be required so that these measurements can be taken and the gate can be fabricated prior to demolition of the pipe connection between the two structures. Temporary bypass pumping will be required in order to remove the pipe segment connecting the Junction Structure to the Drop Structure.

9. For suggested sequence of construction refer to the Special Provision for the "INTERCEPTOR NO. 9 STRUCTURE."

10. The Contractor must provide a temporary soil retention system to protect the Interceptor No. 9 Structure when excavating for the New Miner Street Gate Structure which is at a lower elevation. Refer to the General Notes on drawing SGN-1. This work will not be measured for payment but is included in the Interceptor No. 9

REVISION	
DATE	DESCRIPTION

SHEET 138 OF 167

**SMWRD-1** FR-416

SCALE: NONE