F.A RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
337	19R-1	LAKE	800	53	
STA.		TO STA.			
FFD. RO	AD DIST. NO.	THE TNOTS FED.	ATD PROJ	FCT	

INLET FILTERS

QUANTITIY PROVIDED AT EVERY PROPOSED STRUCTURE LOCATION DURING CONSTRUCTION

PROJECT TOTAL 510

TEMPORARY DITCH CHECKS SCHEDULE

LOCATION	EACH												
	STAGE 1A	STAGE 1B	STAGE 2A	STAGE 2B	STAGE 3A	STAGE 3B	STAGE 4A	STAGE 4B	STAGE 5A	STAGE 5B	STAGE 5C	STAGE 6A	STAGE 6B
ILL. RT. 22 - BEGINNING TO U.S. RT 12 (RAND RD.)	1	16	1	0	0	0	1	0	0	0	0	0	0
ILL. RT. 22 - U.S. RT 12 (RAND RD.) TO MAIN ST. WEST	5	18	0	0	0	8	1	0	1	0	0	0	0
ILL. RT. 22 - MAIN ST. WEST TO OLD RAND RD.	12	0	5	0	1	0	0	0	8	0	0	0	0
ILL. RT. 22 - OLD RAND RD. TO END	6	0	12	0	2	0	0	0	7	0	0	0	0
U. S. RT. 12 (RAND RD.)	7	3	0	0	0	0	0	0	0	0	0	.0	0
MAIN ST. WEST (OLD ILL. RT. 22)	0	0	0	0	0	0	1	0	0	0	0	0	0
OLD RAND RD.	0	0	0	0	7	0	0	0	3	O'	0	0	0
MAIN ST. EAST	0	0	0	0	0	0	0	0	0	0	0	0	0
BEUSCHING RD.	0	0	0	0	1	0	0	0	0	0	0	0	0
STAGE TOTALS	31	37	18	0	11	8	3	0	19	0	0	0	0
			L		d	<u> </u>	<u> </u>				Р	ROJECT TOTAL	127

QUANTITY PROVIDED FOR TEMPORARY DITCH CHECKS (1 EACH) CALCULATED USING STRAW BALE METHOD.

NOTE: PERIMETER EROSION BARRIER, TEMPORARY DITCH CHECKS AND INLET AND PIPE PROTECTION WILL BE CONSTRUCTED AS SHOWN ON STANDARD 280001 AND AS DIRECTED BY THE ENGINEER. MAINTENANCE AND CLEANING OF THE EROSION CONTROL ITEMS WILL BE INCLUDED IN THE RESPECTIVE EROSION CONTROL PAY ITEMS.

REVISIONS		71	I THOTS DEP	ARTMENT	OF TRANSPOR	TATION
NAME	DATE	11-				INITON
REVISED GEOMETRY	11/24/04		ILL	INOIS F	ROUTE 22	
FROM STA, 6+922,366 TO		FF	ROM US R	TE 12	TO BUESCHI	NG RD
STA. 7+440.820		TEI	MPORARY	EROSIO	N CONTROL	PLANS
			SCHEDI	JLE OF	QUANTITIE	S
					DRAWN BY	RLS
		DATE	7/21/04		CHECKED BY	MBF