

COUNTY SHEETS NO.

LAKE 800 518 F.A. . RTE. SECTION 337 19R-1 STA. TO STA. FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT

CONTRACT NO. 60997

TEMPORARY CABLE DIAGRAM LEGEND

- TEMPORARY TRAFFIC SIGNAL SECTION OR PEDESTRIAN SIGNAL SECTION 12" (300 mm)
- TEMPORARY CONTROLLER CABINET
- TEMPORARY SERVICE INSTALLATION
- INDICATES NUMBER OF CONDUCTORS IN CABLE. ALL CONDUCTORS TO BE NUMBER 14 AWG WIRE UNLESS OTHERWISE NOTED.
- ► EMERGENCY VEHICLE LIGHT DETECTOR
- CONFIRMATION BEACON
- VEHICLE DETECTOR, INDUCTION LOOP
- PEDESTRIAN PUSHBUTTON DETECTOR
- 12" (300mm) PEDESTRIAN SIGNAL SECTION
- VIDEO DETECTION

CONSTRUCTION NOTES

1. THE EXISTING TRAFFIC SIGNAL CLOSED LOOP SYSTEM OPERATION SHALL BE MAINTAINED DURING CONSTRUCTION.

CABLE PLAN

- 2. THE CONTRACTOR SHALL MAINTAIN THE EXISTING SIGNAL SYSTEM INTERCONNECT DURING TEMPORARY SIGNAL OPERATION.
- 3. SEE MAINTENANCE OF TRAFFIC PLANS FOR DETAILS OF CONSTRUCTION STAGING

THE TEMPORARY TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION		
NAME	DATE	TEETHOTS DELANTIMENT OF THANSFORTATION		
		TEMPORARY CABLE PLAN &		
		TEMPORARY PHASE DESIGNATION DIAGRAM		
		IL RTE 22 & OLD RAND ROAD		
		DRAWN BY VAP		

SCALE : N.T.S DATE : 07/21/04

BY VAP DESIGNED BY RAM CHECKED BY DDL

	OLD RAND RD						
M	ERGENCY VEHICLE	RGENCY VEHICLE PREEMPTION SEQUENCE					
	TEMPORARY EMERGENCY	VEHICLE PR	EEMPTOR				
EMERGENCY VEHICLE PREEMPTOR		3	4				

TEMPORARY EMERGENCY	VEHICLE PREEMPTOR		
EMERGENCY VEHICLE PREEMPTOR	3	4	
MOVEMENT	*		

TRAFI ELECTRI	TOTAL				
TYPE	NO. LAMPS>	1		20PERATION	WATTAGE
SIGNAL (RED)	12	135	17	0.50	810
(YELLOW)	12	135	25	0.25	405
(GREEN)	12	135	15	0.25	405
ARROW	16	135	12	0.10	216
PED. SIGNAL	0	90	25	1.00	
CONTROLLER	1	100	100	1.00	100
ILLUM. SIGN		84		0.05	
FLASHER				0,50	
ENERGY COSTS	TO:			TOTAL =	1936
ENERGY SUPPLY	201 WEST I SCHAUMBUR	CENTER C RG, ILLING TERI	COURT		ORTATION

COMPANY: COM. EDISON