

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2002-022 K	WILL	172	3
STA. 10+00		TO STA. 22+96.05		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62389				

URBAN
90% R.O.
10% STATE

CODED PAY ITEM NO.	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	RAMP A	RAMP B	RAMP C	RAMP D	EXIT ONLY LN	ILL RTE 53	TS S. RAMP	TS N. RAMP	LIGHTING	SIGNING	SURVEILLANCE
				J000-2A	J000-2A	J000-2A	J000-2A	I000-2A	J000-2A	Y031-1F	Y031-1F	Y030-1E	Y002-1C	Y032-1F
* A2007620	TREE, TAXADIUM DISTICUM (BALD CYPRESS) 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	8		8									
* C2013024	SHRUB, VIBURNUM TRILOBA 'ALFREDO' (AMERICAN CRANBERRY VIBURNUM), 2' BALLED AND BURLAPPED	EACH	35		35									
20100700	TREE REMOVAL (UNDER 6 INCH DIAMETER)	IN DIA	25						25					
20101000	TEMPORARY FENCE	FOOT	2287	435	751	1101								
* 20101400	NITROGEN FERTILIZER NUTRIENT	POUND	699	53	461	13	71		101					
* 20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	699	53	461	13	71		101					
* 20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	699	53	461	13	71		101					
* 20101700	SUPPLEMENTAL WATERING	UNIT	156	12	103	3	16		22					
20200100	EARTH EXCAVATION	CU YD	5962	281	1573	8	306	1465	2329					
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	100		100									
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5088	286	1550	5	252	2556	439					
20400800	FURNISHED EXCAVATION	CU YD	3750	0	3130	0	0	620	0					
20700220	POROUS GRANULAR EMBANKMENT	CU YD	520		239				281					
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	231					231						
20800150	TRENCH BACKFILL	CU YD	2259	38	1002		45	838	336					
20900410	SAND BACKFILL	CU YD	44					44						
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7874	672	2425	49	417	3162	1149					
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	1553	10	48	0.2	4	37	1455					
* 25000210	SEEDING, CLASS 2A	ACRE	3.68	0.23	1.23	0.04	0.42	1.2	0.56					
* 25000750	MOWING	ACRE	3.21	0.24	2.12	0.06	0.33		0.46					
* 25000775	SELECTIVE MOWING STAKES	EACH	12		12									
* 25003210	INTERSEEDING, CLASS 2A	ACRE	0.23		0.23									
* 25100105	MULCH, METHOD 1	ACRE	0.23		0.23									
* 25100630	EROSION CONTROL BLANKET	SQ YD	1137	1137										
* 25200100	SODDING	SQ YD	1473		1473									
* 25200110	SODDING, SALT TOLERANT	SQ YD	17636	5529	1649	1839	2633	162	5824					
* 25300600	TRANSPLANTED SALVAGED TREES	EACH	8						8					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	363	114	34	38	54	3	120					
28000300	TEMPORARY DITCH CHECKS	EACH	10	3		6			1					
28000400	PERIMETER EROSION BARRIER	FOOT	6212	760	119	1458	1446	103	2326					
28000500	INLET FILTERS	EACH	26	7	7	5	0		7					
28000900	FENCE (EROSION CONTROL)	FOOT	5217	1268	119	1458	1446	103	823					
28001000	AGGREGATE (EROSION CONTROL)	TON	10		10									
K0029622	BROADLEAF WEED CONTROL IN TURF	GALLON	1.5			1.5								
31200100	STABILIZED SUB-BASE 4"	SQ YD	4455		4455									
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	5343		1596			3747						
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1240						1240					
X4066450	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", NI05	TON	449		134			315						
X4066620	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, NI05	TON	673		201			472						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.05		0.91			2.14						
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	9558		4557		1185		3816					
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	2659	239		85	315		2020					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	26						26					
44000100	PAVEMENT REMOVAL	SQ YD	5291		2792		805	1694						
44000300	CURB REMOVAL	FOOT	105						105					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5354	329	382	277	360		4006					
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	14963						14963					
44002470	GUTTER INLET REMOVAL	EACH	11			1	2		3					
44002805	ISLAND REMOVAL	SQ FT	2667	1015	833	531	288							
44004250	PAVED SHOULDER REMOVAL	SQ YD	5476	279	2744	36	706	1711						
X0320815	SLEEPER SLAB	FOOT	430		236		194							
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SQ YD	154						154					
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	305	86				219						
48202800	BITUMINOUS SHOULDERS SUPERPAVE 10"	SQ YD	5233	257	1710	37	656	2573						
X0322323	WEED CONTROL, TEASEL	GALLON	1		1									
20001050	AGGREGATE SUBGRADE 12"	SQ YD	15429	219	5790	12	795	3747	4866					
50104400	CONCRETE HEADWALL REMOVAL	EACH	2		2									
50104650	SLOPE WALL REMOVAL	SQ YD	319						319					
50200100	STRUCTURE EXCAVATION	CU YD	853		313				540					

□ NON-PARTICIPATING
* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES
NAME	DATE	
SCALE: NTS	DRAWN BY: CC	CHECKED BY: RI
DATE: 1/6/2005		

DMJM HARRIS
303 East Wacker Drive, Suite 600
Chicago, Illinois, 60601 Phone: 312.321.6101 Fax: 312.396.2392

PLAN
DATE: _____
BY: _____
SURVEYED: _____
CHECKED: _____
ALIGNED: _____
NOTED: _____
FILE NAME: _____

PROFILE
DATE: _____
BY: _____
SURVEYED: _____
CHECKED: _____
STRUCTURE: _____
ROTATING CHRD: _____