

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2002-022 K	WILL	172	8
STA. 10+00		TO STA. 22+96.05		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62389				

EARTHWORK SCHEDULE

LOCATION	STATION TO	STATION	UNDERCUT (CY)			PGE (CY)			UNSUITABLE EXCAVATION (TOPSOIL) (CY)			EARTH EXCAVATION (CY)			STRUCTURE EXCAVATION (CY)			TOTAL SUITABLE EXCAVATION (CY)			EXC. TO BE USED IN EMBANKMENT (ADJ. FOR SHINKAGE) 15% (CY)			EMBANKMENT (CY)			EARTH BALANCE WASTE (+) OR SHORTAGE (-) (CY)			TOPSOIL FURNISH AND PLACE 4" (CY)			
			P	1	2	P	1	2	P	1	2	P	1	2	P	1	2	P	1	2	P	1	2	P	1	2	P	1	2				
RAMP A	300+73	-	303+61	0	0	0	0	0	0	0	95	191	0	62	219	0	0	0	0	62	219	0	52	186	0	41	44	0	11	142	0	160	512
RAMP B	10+72	-	22+96	0	0	0	0	0	239	0	1391	158	12	913	649	0	313	0	12	1226	649	10	1042	551	0	4083	641	10	-3041	-90	0	1734	646
RAMP C	611+30	-	612+77	0	0	0	0	0	0	0	5	0	0	8	0	0	0	0	0	8	0	0	7	0	0	0	0	0	7	0	0	49	0
Frontage	400+54	-	498+78	0	0	0	0	0	0	0	6	0	0	5	0	0	0	0	0	5	0	0	5	0	0	0	0	0	5	0	0	12	33
RAMP D	105+45	-	111+88	0	0	0	0	0	0	0	90	162	0	99	207	0	0	0	0	99	207	0	84	176	0	50	112	0	34	64	0	192	225
I-55 Aux. Lane	0+00	-	23+00	0	150	81	0	150	81	0	2324	0	0	1404	61	0	0	0	0	1404	61	0	1193	52	0	1865	0	0	-672	52	0	3162	0
IL RTE 53	1454+20	-	1466+96	0	0	0	0	0	281	0	122	311	0	651	1673	0	0	540	0	651	2213	0	554	1881	0	89	59	0	2	1821	0	447	702
TOTALS				0	150	81	0	150	601	0	4033	823	12	3142	2809	0	313	540	12	3455	3349	10	2937	2846	0	6128	857	10	-3654	1990	0	5756	2118

PLAN SURVEYED BY: DATE: []

NOTED BY: []

NOTE BOOK NO. []

ADD TILL NAME []

PROFILE SURVEYED BY: DATE: []

NOTED BY: []

NOTE BOOK NO. []

STRUCTURE NO./A/S/CP/NO []

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NTS

DATE: 12/23/2004

DRAWN BY: CC

CHECKED BY: RI

DMJM HARRIS

303 East Wacker Drive, Suite 600
Chicago, Illinois, 60601 Phone: 312.321.6101 Fax: 312.396.2392