

SCHEDULE OF QUANTITIES

CODED PAY ITEM	PAY ITEM	SIGN NO. STATION SIZE (HEIGHT X LENGTH)	UNIT	TOTAL	STATION										LOGO & EXIT VARIOUS			
					484+06	484+79	485+00	485+30	486+80	488+30	494+61.3	499+60	511+61.2	519+00		531+00		
					6'-0" x 13'-6"	10' 0" x 12'-0"	6'-0" x 13'-6"	10' 0" x 12'-0"	10' 0" x 12'-0"	12'-6" x 17'-0"	12'- 6" x 17'-0"	12'-6" x 17'-0"	12'-6" x 17'-0"	12'-6" x 15'-6"		12'-6" x 15'-6"		
												11'-0" x 12'-6"	11'-0" x 12'-6"					
72000300	SIGN PANEL - TYPE 3	SQ FT	1,104.0			81.0						212.5		350.0	350.0	193.8	193.8	45.0
72400330	REMOVE SIGN PANEL-TYPE 3	SQ FT	671.5	81.0						212.5			350.0					
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	460.0		120.0		120.0	120.0										100.0
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKWAY	POUND	3,046.0		585.0	274.0	585.0	702.0									900.0	
73000100	WOOD SIGN SUPPORT	FOOT	86.0															86.0
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" x 4'-6")	FOOT	80.0											80.0				
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" x 7'-0")	FOOT	60.1							29.6						30.5		
73400100	CONCRETE FOUNDATIONS	CU YD	44.8		1.4	1.4	1.4	1.4		9.0		17.5	8.9			3.8		
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	30.8							9.0		12.9	8.9					
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.0											1				
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.0						1									
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	8.0	2	2		2	2										
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	8.0	2	2		2	2										
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	3.0						1				2					
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	89.0							21.0		40.0	28.0					

PLAN
REVISIONS
CHECKED
DATE
BY
NOTE BOOK
NO.

PROFILE
REVISIONS
CHECKED
DATE
BY
NOTE BOOK
NO.

SGN-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES



KAM ENGINEERING, INC.
CONSULTING ENGINEERS
707A Davis Road, Suite 205
Eglin, Illinois 6023-569

SCALE: NONE
DATE: DECEMBER, 2004

DRAWN BY: RV
DESIGNED BY: AS
CHECKED BY: SL

2-10-05