


EAST SKYWAY SHELTER (RO3) FOUNDATION PLAN NOT TO SCALE




I-55 SHELTER (RO1) FOUNDATION PLAN NOT TO SCALE

Edwards AND Kelcey

-3'X5' CONCRETE STOOP. SEE DETAIL SHEET COMM-92. (COORDINATE LIFT POINT LOCATIONS IN FIELD WITH SHELTER DROP) -TIE DOWN BRACKET (TYPICAL OF 4) SEE BUILDING ATTACHMENT DETAIL THIS SHEET. ANCHOR PLATES ATTACHED TO SHELTER LIFT POINTS 000000 PROVIDE SLAB OPENING FOR

(6) 4" DIA. SCH. 80 PVC CONDUIT
STUBS. COORDINATE LOCATION
WITH COMMUNICATION VAULT.
SEE SHEET COMM-80 FOR DETAILS. +/- 11.00' WITH SHELTER INTERIOR FOUNDATION WALL-**▼**A EDGE OF SLAB & -EXTERIOR FACE OF PREFAB SHELTER (CONFIRM WITH SHELTER MANUFACTURER) +/- 13.00' TIE DOWN BRACKET (TYP, OF 4) MAINTENANCE YARD SHELTER (RO2) FOUNDATION PLAN



NOTES:

- NOTES:

 1. CONTRACTOR SHALL DEBURR ALL SHARP EDGES AND HOLES.

 2. SURFACING OF FINISHED SLAB SHALL BE LEVEL & FLAT WITHIN +/- 1/4".

 3. CONTRACTOR SHALL COORDINATE THE INSTALLATION OF SHELTER ON TO ITS FOUNDATION WITH THE SHELTER FABRICATOR.

 4. ALL REINFORCING BARS SHALL BE EPOXY COATED AND SHALL BE WIRE LASHED AT ALL INTERSECTIONS.

 5. IF ROCK IS ENCOUNTERED, CONTRACTOR SHALL CONTACT ENGINEER IMMEDIATELY, DO NOT PROCEED UNTIL ENGINEER ISSUES REVISED FOUNDATION DESIGN BASED ON SUBSURFACE CONDITIONS.

 6. COORDINATE CONDUIT ENTRY LOCATION WITH ENGINEER PER SITE PLAN DETAIL SHEET AND COMMUNICATION SHELTER FOUNDATION.

COMM-91

COUNTY TOTAL SHEET NO.

SECTION 94/90 2003-031I

62583

TO STA.

FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT

STA.

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME DATE	TECTIONS DEL'ANTIMENT	OF TRANSFORTATION
	F.A.I. 94/90 (DAN R	RYAN EXPRESSWAY)
	31st STREET	T to I-57
	SHELTER FOUNDATION DETAILS (SHEET 1 OF 2)	
]	
	SCALE: NOT TO SCALE	DRAWN BY: JM
****	DATE: October 29, 2004	CHECKED BY: CS