

	SECTION	N	COUNTY	TOTAL SHEETS	SHEET NO.
	2003-031	I	COOK	976	914
STA.		то	STA.		
FED. RO	AD DIST. NO	ILLINOIS	FED. AID	PROJECT	
	62583		***************************************		

## NOTES:

- 1. ALL DIMENSIONS ARE IN INCHES.
- TOP AND BOTTOM CABLE ENTRY AVAILABLE THROUGH REMOVABLE ACCESS PLATES. REMOVE, PUNCH TO SUIT CONDUIT SIZE, AND REPLACE.
- 3. CONTROL WIRING AND POWER WIRING MUST BE RUN IN SEPARATE CONDUIT. OUTPUT CABLES MUST BE RUN IN A SEPARATE CONDUIT FROM INPUT
- 4. ALUMINUM AND COPPER CLAD ALUMINUM CABLES ARE NOT RECOMMENDED.
- 5. ALL WIRING IS TO BE IN ACCORDANCE WITH NATIONAL AND LOCAL ELECTRICAL CODES.





D

DT-12G

		D1-12G	
REVISIONS NAME DAT	ILLINOIS DEPARTMENT OF TRANSPORTATION		
		N RYAN EXPRESSWAY)	
	31st ST	REET to I-57	
	TERMINAL DETAILS 40 KVA UPS MODULE		
	SCALE; NOT TO SCALE	DRAWN BY: SST	
	DATE: October 29, 2004	CHECKED BY: CS	

