

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN 1) WITH INSTALLED PANEL 2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 2.3 SQ. M. (25.70 SQ. FT.)

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES)
UNLESS OTHERWISE SHOWN.

REVISIONS
ILLINOIS DEPARTMENT OF TRANSPORTATION
R, MIRS 9-15-97
R, MIRS 12-11-97
T. RAMMACHER 2-2-99

SCALE: DRAWN BY: BUR. OF DESIGN
DATE 10/18/2002 CHECKED BY

Friday October 18, 2002 & 10:25:17 AM c:\projects\diststd\to22.dgn LV=35,63 VI=TC22

REVISION DATE: 02/02/99