							0 10
	F. A.S. RTE.	SECTION			COUNTY	TOTAL SHEETS	SHEET NO
	1197	7 105 BR-2 & 105-T			TESIDE	59	46
	STA. 2	+00 & 425+	-38				
FED. ROAD DIST, NO. ILLING			IS FED. AID PROJECT				

TREE REPLACEMENT SCHEDULE STA. 224+00 & 2

GENERAL NOTES:

- 1. TREE LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT.
- 2. MULCH SHALL BE HARDWOOD WOOD CHIPS, 5 FOOT WIDTH, 4 INCHES THICK WITH WEED BARRIER FABRIC.
- 3. ALTERNATE SITE: TBD BY DISCTRICT 2.

SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	LOCATION	QUANTITY
TREE, QUERCUS BICOLOR	SWAMP WHITE OAK	1-3/4" CALIPER, BALLED & BURLAPPED	EACH	SEE ABOVE NOTE	12

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES)
UNLESS OTHERWISE NOTED.