

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	11
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	PAY ITEMS	UNIT	100% STATE														
			URBAN	J000-2A	SFTY-3N	X028-2A	X271-2A	Y007	Y030-1E	Y031-1F	Y077	Y079	SFTY-3C	Y002-1C			
			TOTAL QUANTITY	P. C. CONCRETE	IMPACT ATTEN.	STRUCTURES	STRUCTURES	MINOR STRUCT.	HWY. LIGHTING	SIGNALS	WETLANDS	HAZ. WASTE	BREAKAWAY	TRAFFIC SIGNS			
60270055	DRAINAGE STRUCTURES, TYPE 5 WITH TWO TYPE 22 FRAMES AND GRATES	EACH	1	1													
60500040	REMOVING MANHOLES	EACH	4	4													
60500060	REMOVING INLETS	EACH	34	34													
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	2	2													
60500105	FILLING MANHOLES	EACH	6	6													
60600095	CLASS S1 CONCRETE (OUTLET)	C. Y.	7.8	7.8													
60600605	CONCRETE CURB, TYPE B	FT.	227	227													
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	FT.	9,997	9,997													
60605400	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24 (SPECIAL)	FT.	609	609													
60608521	COMBINATION CONCRETE CURB & GUTTER, TYPE M-2.24	FT.	50	50													
60608600	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.06	FT.	127	127													
60610400	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.24	FT.	1,193	1,193													
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	S. F.	16,096	16,096													
60619100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	S. F.	6,109	6,109													
60624600	CORRUGATED MEDIAN	S. F.	873	873													
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	1	1													
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	2	2													
60900515	CONCRETE THRUST BLOCKS	EACH	24	24													
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FT.	2,116	2,116													
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3													
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	5	5													