CONTRACT NO. 64647

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 595 | 1-3-K | ROCK ISLAND | 476 | 48 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

# SCHEDULE OF QUANTITIES

| | | |
|---|---|---|
| 50104400 CONCRETE HEADWALL REMOVAL | | EACH |
| JOHN DEERE ROAD | | |
| RT. STA. 409+98 | | 1 |
| LT. STA. 411+06 | | 1 |
| | TOTAL | 2 |
| 50105200 REMOVE EXISTING CULVERTS | | EACH |
| 52ND AVENUE | | |
| LT. & RT. STA. 1169+70 | | 1 |
| LT. & RT. STA. 1169+82 | | 1 |
| LT. & RT. STA. 1169+93.5 | | 1 |
| | TOTAL | 3 |
| 50300255 CONCRETE SUPERSTRUCTURE | | C.Y. |
| MILAN BELTWAY | | |
| RT. STA. 364+21.36-364+38.84 | | 2.15 |
| RT. STA. 381+17.45-381+36.22 | | 2.15 |
| | TOTAL | 4.30 |
| 54001001 BOX CULVERT END SECTIONS, CULVERT NO. 1 | | EACH |
| 44TH STREET CONNECTOR | | |
| LT. & RT. STA. 3+19.43 | | 2 |
| | TOTAL | 2 |
| 54001002 BOX CULVERT END SECTIONS, CULVERT NO. 2 | | EACH |
| JOHN DEERE ROAD | | |
| LT. & RT. STA. 393+50 | | 2 |
| | TOTAL | 2 |
| 54020303 PRECAST CONCRETE BOX CULVERT 3'X3' (M273) | | FT. |
| 44TH STREET CONNECTOR | | |
| A.R. STA. 3+19.43 | | 50 |
| | TOTAL | 50 |
| 54020502 PRECAST CONCRETE BOX CULVERT 5'X2' (M273) | | FT. |
| JOHN DEERE ROAD | | |
| LT. & RT. STA. 393+50 | | 146 |
| | TOTAL | 146 |
| 542A0223 PIPE CULVERT, CLASS A, TYPE 1, 18" | | FT. |
| 44TH STREET CONNECTOR | | |
| LT. & RT. STA. 5+68.44 | | 44 |
| | TOTAL | 44 |
| 542A1060 PIPE CULVERT, CLASS A, TYPE 2, 15" | | FT. |
| 52ND AVENUE | | |
| RT. STA. 1169+28+7-1169+78.7 | | 50 |
| | TOTAL | 50 |
| 542A3391 PIPE CULVERT, CLASS A, TYPE 5, 36" | | FT. |
| 52ND AVENUE | | |
| LT. & RT. STA. 1157+72.4 | | 206 |
| | TOTAL | 206 |
| 54213657 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | | EACH |
| JOHN DEERE ROAD | | |
| RT. STA. 399+50 | | 1 |
| RT. STA. 401+65 | | 1 |
| RT. STA. 403+80 | | 1 |
| RT. STA. 406+00 | | 1 |
| RT. STA. 408+50 | | 1 |
| RT. STA. 411+00 | | 1 |
| RT. STA. 414+65 | | 1 |
| 52ND AVENUE | | |
| LT. STA. 1167+50 | | 1 |
| RAMP 1 | | |
| RT. STA. 1+15 | | 1 |
| VALLEY VIEW | | |
| RT. STA. 152+75 | | 1 |
| RT. STA. 166+70.68 | | 1 |
| RT. STA. 167+48.22 | | 1 |
| | TOTAL | 12 |
| 54213660 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15" | | EACH |
| JOHN DEERE ROAD | | |
| RT. STA. 396+00 | | 1 |
| 52ND AVENUE | | |
| RT. STA. 1169+22.4 | | 1 |
| RT. STA. 1169+84.9 | | 1 |
| | TOTAL | 3 |
| 54213663 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" | | EACH |
| BLACKHAWK ROAD | | |
| LT. STA. 1153+00 | | 1 |
| 44TH STREET CONNECTOR | | |
| LT. & RT. STA. 5+68.44 | | 2 |
| | TOTAL | 3 |
| 54213669 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" | | EACH |
| JOHN DEERE ROAD | | |
| RT. STA. 388+25 | | 1 |
| RELOCATED THIRD STREET | | |
| RT. STA. 7+50 | | 1 |
| | TOTAL | 2 |
| 54213681 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36" | | EACH |
| VALLEY VIEW | | |
| LT. STA. 152+15 | | 1 |
| RT. STA. 152+60 | | 1 |
| 52ND AVENUE | | |
| LT. & RT. STA. 1157+72.4 | | 2 |
| | TOTAL | 4 |
| 54215547 METAL END SECTIONS 12" | | EACH |
| MILAN BELTWAY | | |
| LT. STA. 356+91 | | 1 |
| RT. STA. 356+91 | | 1 |
| 52ND AVENUE | | |
| LT. STA. 1157+93.50 | | 1 |
| RT. STA. 1160+75 | | 1 |
| LT. STA. 1160+75 | | 1 |
| RT. STA. 1163+00 | | 1 |
| LT. STA. 1163+25 | | 1 |
| RT. STA. 1164+55 | | 1 |
| LT. STA. 1165+50 | | 1 |
| LT. STA. 1167+50 | | 1 |
| RAMP 1 | | |
| RT. STA. 1+37.50 | | 1 |
| VALLEY VIEW | | |
| RT. STA. 154+00 | | 1 |
| RT. STA. 155+50 | | 1 |
| RT. STA. 157+75 | | 1 |
| LT. STA. 160+15 | | 1 |
| RT. STA. 160+60 | | 1 |
| RT. STA. 161+50 | | 1 |
| LT. STA. 161+50 | | 1 |
| RT. STA. 163+25 | | 1 |
| LT. STA. 163+25 | | 1 |
| RT. STA. 165+00 | | 1 |
| LT. STA. 165+00 | | 1 |
| | TOTAL | 22 |
| 54215550 METAL END SECTIONS 15" | | EACH |
| MILAN BELTWAY | | |
| RT. STA. 364+00 | | 1 |
| BLACKHAWK ROAD | | |
| LT. STA. 1154+00 | | 1 |
| | TOTAL | 2 |
| 54248510 CONCRETE COLLAR | | C.Y. |
| 68' RT. STA. 166+84.5 | | 0.11 |
| 43' RT. STA. 167+26.4 | | 0.11 |
| | TOTAL | 0.22 |
| 550A0050 STORM SEWERS, CLASS A, TYPE 1 12" | | FT. |
| 52ND AVENUE | | |
| LT. STA. 211+15-211+90 | | 70 |
| LT. STA. 211+90-213+15 | | 120 |
| RT. STA. 211+75-213+00 | | 118 |
| LT. STA. 214+50-215+75 | | 120 |
| VALLEY VIEW | | |
| RT. STA. 166+75.16-166+84.35 | | 12 |
| RT. STA. 167+25.84-167+43.61 | | 24 |
| TRINITY DRIVE | | |
| RT. STA. 1+76.48 | | 8 |
| RELOCATED THIRD STREET | | |
| LT. STA. 11+38-RT. STA. 11+43.88 | | 41 |
| RT. STA. 11+43.88-11+43.15 | | 18 |
| | TOTAL | 531 |
| 550A0070 STORM SEWERS, CLASS A, TYPE 1 15" | | FT. |
| 52ND AVENUE | | |
| LT. STA. 1174+15-211+15 | | 68 |
| | TOTAL | 68 |
| 550A0340 STORM SEWERS, CLASS A, TYPE 2 12" | | FT. |
| MILAN BELTWAY | | |
| STA. 358+90-360+90 | | 197 |
| STA. 360+90-362+90 | | 197 |
| JOHN DEERE ROAD | | |
| STA. 383+50-386+00 | | 246 |
| STA. 390+50-392+13.86 | | 160 |
| STA. 393+40-393+50 | | 6 |
| RT. STA. 396+00 | | 78 |
| STA. 396+00-397+80 | | 176 |
| RT. STA. 399+50 | | 78 |
| RT. STA. 401+65 | | 78 |
| RT. STA. 403+80 | | 78 |
| RT. STA. 406+00 | | 78 |
| RT. STA. 408+50 | | 80 |
| RT. STA. 411+00 | | 94 |
| RT. STA. 414+65 | | 90 |
| STA. 414+65-415+75 | | 106 |
| BLACKHAWK ROAD | | |
| RT. STA. 1142+72.4 | | 14 |
| RT. STA. 1142+72.4-1144+16 | | 138 |
| RT. STA. 1146+25-1147+10 | | 78 |
| RT. STA. 1147+10-1147+21.4 | | 6 |
| RT. STA. 1148+50-LT. STA. 1148+55 | | 40 |
| LT. STA. 1148+55-1148+65 | | 12 |
| LT. STA. 1148+65-1148+80 | | 32 |
| RT. STA. 1148+50-1150+25 | | 160 |
| LT. STA. 1148+55-1149+75 | | 122 |
| LT. STA. 1149+75-1149+80 | | 10 |
| LT. STA. 1149+80-1150+00 | | 34 |
| RT. STA. 1151+75-1152+50 | | 64 |
| RT. STA. 1152+50-1152+75 | | 48 |
| RT. STA. 1152+75-LT. STA. 1152+67.5 | | 16 |
| LT. STA. 1152+67.5-1153+00 | | 52 |
| RT. STA. 1154+00-1154+20 | | 44 |
| STA. 1154+20 | | 16 |
| 52ND AVENUE | | |
| STA. 1167+50 | | 76 |
| RT. STA. 1169+75 | | 10 |
| LT. STA. 1169+50 | | 10 |
| LT. STA. 1171+40-RT. STA. 1171+75 | | 86 |
| STA. 0+84.75 (TRINITY DR.)-1173+00 | | 116 |
| RT. STA. 214+25-215+75 | | 144 |
| RT. STA. 215+75-216+52.4 | | 72 |
| RT. STA. 216+52.4-217+00 | | 42 |
| LT. STA. 215+75-216+52.4 | | 72 |
| LT. STA. 216+52.4-217+00 | | 42 |
| STA. 217+00 | | 48 |
| RAMP 1 | | |
| STA. 1157+15-1+15 | | 98 |
| VALLEY VIEW | | |
| STA. 152+75 | | 40 |
| RT. STA. 168+64.2-0+80.6(OLD BLACKHAWK ROAD) | | 92 |
| STA. 171+20 | | 26 |
| RT. STA. 172+24-152+72 | | 45 |
| RELOCATED THIRD STREET | | |
| LT. STA. 0+42.5-1+25 | | 76 |
| LT. STA. 1+25-2+25 | | 94 |
| RT. STA. 2+00-3+14.53 | | 109 |
| STA. 3+14.53 | | 30 |
| STA. 10+00 | | 30 |
| RT. STA. 10+00 | | 6 |
| | TOTAL | 3,992 |