

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	50
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH			
	MILAN BELTWAY				
	LT. STA. 361+00	1			
	RT. STA. 361+00	1			
	RT. STA. 364+05	1			
	LT. STA. 364+21	1			
	JOHN DEERE ROAD				
	RT. STA. 389+25	1			
	LT. STA. 392+25	1			
	LT. STA. 396+00	1			
	LT. STA. 400+00	1			
	RT. STA. 400+00	1			
	RT. STA. 404+00	1			
	LT. STA. 405+00	1			
	RT. STA. 408+00	1			
	RT. STA. 412+00	1			
	LT. STA. 414+70	1			
	RAMP 1				
	LT. STA. 4+00	1			
	LT. STA. 8+00	1			
	RT. STA. 9+00	1			
	RT. STA. 13+50	1			
	RAMP 2				
	LT. STA. 9+50	1			
	LT. STA. 12+50	1			
	RAMP 3				
	RT. STA. 6+50	1			
	RT. STA. 9+50	1			
	LT. STA. 13+50	1			
	RAMP 4				
	RT. STA. 4+50	1			
	RT. STA. 8+50	1			
	RT. STA. 11+50	1			
	TOTAL	26			
60100945	PIPE DRAINS 12"	FT.			
	MILAN BELTWAY				
	LT. STA. 356+91	46			
	RT. STA. 356+91	72			
	52ND AVENUE				
	LT. STA. 1157+93.5	78			
	RT. STA. 1160+75	75			
	LT. STA. 1160+75	75			
	RT. STA. 1163+00	94			
	LT. STA. 1163+25	81			
	RT. STA. 1164+72.5	92			
	LT. STA. 1165+50	68			
	LT. STA. 1167+50	66			
	RAMP 1				
	RT. STA. 1+37.50	78			
	VALLEY VIEW				
	RT. STA. 154+00	30			
	RT. STA. 155+50	38			
	RT. STA. 157+75	32			
	LT. STA. 160+15	34			
	RT. STA. 160+60	36			
	RT. STA. 161+50	76			
	LT. STA. 161+50	40			
	RT. STA. 163+25	38			
	LT. STA. 163+25	40			
	RT. STA. 165+00	26			
	LT. STA. 165+00	26			
	TOTAL	1,241			
60100955	PIPE DRAINS 15"	FT.			
	MILAN BELTWAY				
	RT. STA. 364+00	48			
	BLACKHAWK ROAD				
	LT. STA. 1154+00	76			
	TOTAL	124			
60107600	PIPE UNDERDRAINS 4"	FT.			
	MILAN BELTWAY				
	33.5' RT. STA. 357+13.7-33.5' RT. STA. 361+00	386			
	33.5' LT. STA. 357+13.7-33.5' LT. STA. 361+00	386			
	33.5' RT. STA. 361+00-33.5' RT. STA. 364+05	305			
	33.5' LT. STA. 361+00-33.5' LT. STA. 364+21	321			
	JOHN DEERE ROAD				
	33.5' RT. STA. 384+50.00' RT. STA. 389+25	475			
	33.5' LT. STA. 386+50-33.5' LT. STA. 389+25	275			
	33.5' RT. STA. 389+25-33.5' RT. STA. 392+00	275			
	33.5' LT. STA. 389+25-33.5' LT. STA. 392+25	300			
	33.5' LT. STA. 392+25-33.5' LT. STA. 396+00	375			
	33.5' LT. STA. 396+00-33.5' LT. STA. 400+00	400			
	47.5' RT. STA. 400+00-47.5' RT. STA. 404+00	400			
	33.5' LT. STA. 400+00-33.5' LT. STA. 405+00	500			
	47.5' RT. STA. 404+00-47.5' RT. STA. 408+00	400			
	33.5' LT. STA. 405+00-33.5' LT. STA. 410+00	500			
	47.5' RT. STA. 408+00-47.5' RT. STA. 412+00	400			
	47.5' RT. STA. 412+00-47.5' RT. STA. 415+45	345			
	47.5' LT. STA. 414+70-47.5' LT. STA. 417+10	260			
	RAMP 1				
	16' LT. STA. 1+00-16' LT. STA. 4+00	300			
	16' LT. STA. 4+00-16' LT. STA. 8+00	400			
	STA. 7+50-9+00	150			
	STA. 9+00-13+50	450			
	STA. 13+50-18+50	500			
	RAMP 2				
	24' LT. STA. 4+50-24' LT. STA. 9+50	500			
	24' LT. STA. 9+50-36' LT. STA. 12+50	300			
	36' LT. STA. 12+50-36' LT. STA. 15+50	300			
	RAMP 3				
	STA. 3+65-6+50	385			
	STA. 6+50-9+50	300			
	STA. 9+50-10.4' RT. STA. 13+50	400			
	16' LT. STA. 13+50-12' LT. STA. 17+30	380			
	RAMP 4				
	STA. 0+50-4+50	400			
	STA. 4+50-8+50	400			
	STA. 8+50-11+50	300			
	STA. 11+50-14+27	277			
	TOTAL	12,045			
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FT.			
	MILAN BELTWAY				
	33.5' RT. STA. 361+00	23			
	33.5' LT. STA. 361+00	23			
	33.5' RT. STA. 364+05	23			
	33.5' LT. STA. 364+21	34			
	JOHN DEERE ROAD				
	33.5' RT. STA. 389+25	22			
	33.5' LT. STA. 392+25 (2)	38			
	33.5' LT. STA. 396+00	16			
	47.5' RT. STA. 400+00	20			
	33.5' LT. STA. 400+00	32			
	47.5' RT. STA. 404+00	20			
	33.5' LT. STA. 405+00	20			
	47.5' RT. STA. 408+00	20			
	47.5' RT. STA. 412+00	20			
	47.5' LT. STA. 414+70	18			
	RAMP 1				
	LT. STA. 4+00	16			
	LT. STA. 8+00	16			
	RT. STA. 9+00 (2)	32			
	RT. STA. 13+50	16			
	RAMP 2				
	LT. STA. 9+50 (2)	48			
	LT. STA. 12+50	20			
	RAMP 3				
	RT. STA. 6+50	16			
	RT. STA. 9+50 (2)	32			
	LT. STA. 13+50	16			
	RAMP 4				
	RT. STA. 4+50	16			
	RT. STA. 8+50 (2)	32			
	RT. STA. 11+50	16			
	TOTAL	605			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH			
	MILAN BELTWAY				
	RT. STA. 364+00	1			
	52ND AVENUE				
	SANITARY SEWER				
	37.95' RT. STA. 4+65.55	1			
	28' RT. STA. 8+34.50	1			
	41.96' LT. STA. 1170+31.76	1			
	52.09' LT. STA. 1173+84.08	1			
	50.43' LT. STA. 211+31.19	1			
	34.51' LT. STA. 215+30.88	1			
	28.82' LT. STA. 217+71.97	1			
	18.56' LT. STA. 218+46.24	1			
	VALLEY VIEW				
	LT. STA. 1152+60	1			
	TOTAL	10			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH			
	VALLEY VIEW				
	RT. STA. 152+28.12	1			
	RELOCATED THIRD STREET				
	LT. STA. 4+00	1			
	RT. STA. 7+50	1			
	TOTAL	3			
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH			
	RELOCATED THIRD STREET				
	RT. STA. 10+00	1			
	RT. STA. 11+43.15	1			
	TOTAL	2			
60240220	INLETS, TYPE B, TYPE 3 FRAME & GRATE	EACH			
	BLACKHAWK ROAD				
	LT. STA. 1148+65	1			
	LT. STA. 1149+80	1			
	LT. STA. 1152+67.50	1			
	RT. STA. 1152+75	1			
	RT. STA. 1154+20	1			
	LT. STA. 1154+20	1			
	52ND AVENUE				
	RT. STA. 1157+15	1			
	RT. STA. 1160+75	1			
	LT. STA. 1160+75	1			
	LT. STA. 1163+25	1			
	TOTAL	10			
60240310	INLETS, TYPE B, TYPE 11 FRAME & GRATE	EACH			
	BLACKHAWK ROAD				
	LT. STA. 1148+55	1			
	LT. STA. 1149+75	1			
	TOTAL	2			
60242700	INLETS SPECIAL, NO. 3	EACH			
	52ND AVENUE				
	RT. STA. 1171+75	1			
	RT. STA. 1173+00	1			
	RELOCATED THIRD STREET				
	LT. STA. 3+14.53	1			
	RT. STA. 5+00	1			
	LT. STA. 5+00	1			
	TOTAL	5			
60242801	INLETS SPECIAL, NO. 5	EACH			
	BLACKHAWK ROAD				
	RT. STA. 1142+72.4	1			
	RT. STA. 1144+16	1			
	RT. STA. 1146+25	1			
	RT. STA. 1147+10	1			
	RT. STA. 1147+85	1			
	RT. STA. 1148+50	1			
	LT. STA. 1148+80	1			
	LT. STA. 1150+00	1			
	RT. STA. 1150+25	1			
	RT. STA. 1151+75	1			
	RT. STA. 1152+50	1			
	LT. STA. 1153+00	1			
	RT. STA. 1154+00	1			
	LT. STA. 1154+00	1			