

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	52
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	ITEM NO.	DESCRIPTION	UNIT	QUANTITY
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH		60900315	TYPE D INLET BOX, STANDARD 609006	EACH	
	TRINITY DRIVE				MILAN BELTWAY		
	LT. & RT. STA. 1+62	2			LT. STA. 356+91		1
					RT. STA. 356+91		1
	TOTAL	2			TOTAL		2
60500105	FILLING MANHOLES	EACH		60900515	CONCRETE THRUST BLOCKS	EACH	
	52ND AVENUE				MILAN BELTWAY		
	38' LT. STA. 1164+90	1			RT. STA. 364+00		1
	50' LT. STA. 1164+90	1			BLACKHAWK ROAD		
	47' LT. STA. 1167+44	1			LT. STA. 1154+00		1
	37' LT. STA. 1167+55	1			LT. STA. 1154+00		1
	31' LT. STA. 1170+40	1			52ND AVENUE		
	13' RT. STA. 1171+30	1			LT. STA. 1157+93.50		1
					RT. STA. 1160+75		1
	TOTAL	6			LT. STA. 1160+75		1
60600095	CLASS SI CONCRETE (OUTLET)	C. Y.			RT. STA. 1163+00		1
	RAMP 3				LT. STA. 1163+25		1
	27' LT. STA. 15+34.54-12' LT. STA. 15+79.46	3.92			RT. STA. 1164+55		1
					LT. STA. 1165+50		1
	RAMP 4				LT. STA. 1167+50		1
	29' LT. STA. 2+74.81-12' LT. STA. 2+35.41	3.92			RAMP 1		
					RT. STA. 1+37.50		1
	TOTAL	7.84			VALLEY VIEW		
60600605	CONCRETE CURB, TYPE B	FT.			RT. STA. 152+75		1
	44TH STREET				RT. STA. 154+00		1
	RT. STA. 17+61.58-18+32.17	79.1			RT. STA. 155+50		1
	C.E. LT. STA. 17+02	20.0			RT. STA. 157+75		1
					RT. STA. 160+15		1
	44TH STREET CONNECTOR				LT. STA. 160+15		1
	LT. STA. 0+65.72-1+70.55	127.9			RT. STA. 161+50		1
					LT. STA. 161+50		1
	TOTAL	227.0			RT. STA. 163+25		1
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	FT.			LT. STA. 163+25		1
	JOHN DEERE ROAD				RT. STA. 165+00		1
	STAGE 2 PHASE 3				LT. STA. 165+00		1
	LT. STA. 417+10-176+51	293.5			TOTAL		24
					63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FT.
	JOHN DEERE ROAD					MILAN BELTWAY	
	STAGE 2 PHASE 4					RT. STA. 356+96.53-363+90.56	694.0
	RT. STA. 415+45-416+55	110.0				LT. STA. 357+13.92-364+11.13	697.2
						JOHN DEERE ROAD	
	BLACKHAWK ROAD					RT. STA. 381+49.56-381+74.56	25.0
	LT. STA. 1144+42-1150+52.2	633.6				LT. STA. 381+96.82-383+46.82	150.0
	RT. STA. 1146+00-1156+47.4	1,012.3				52ND AVENUE	
	RT. & LT. STA. 1152+53.57-1156+74.39	835.7				RT. STA. 1157+65.14-1158+02.64	37.5
	LT. STA. 1156+85-1157+00	22.3				LT. STA. 1157+21.71-1157+96.71	75.0
	RT. STA. 1157+00 (E. RADIUS)	125.8				RT. STA. 1160+48.33-1161+85.83	137.5
						LT. STA. 1160+40.76-1163+40.76	300.0
	52ND AVENUE					TOTAL	2,116.2
	RT. STA. 1157+25-1157+78.8	53.8				63100045	TRAFFIC BARRIER TERMINAL, TYPE 2
	RT. STA. 1157+03.6-1158+02.2	98.4					EACH
	LT. STA. 1160+64.4-1163+30	265.6				JOHN DEERE ROAD	
	LT. STA. 1163+55-1172+28.24	873.2				RT. STA. 381+74.56-381+88.81	1
	RT. STA. 1160+64.4-1164+73.7	417.3				52ND AVENUE	
	MEDIAN LT. STA. 1161+66.13-1165+15.69	348.3				LT. STA. 1157+07.46-1157+21.71	1
	MEDIAN RT. STA. 1161+66.13-1165+15.69	349.6				RT. STA. 1161+85.83-1162+00.08	1
	RT. STA. 1164+73.7-1165+68.8 (W. RADIUS)	151.2				TOTAL	3
	RT. STA. 1166+46.9-1167+98 (E. RADIUS)	188.7				63100070	TRAFFIC BARRIER TERMINAL, TYPE 5
	RT. STA. 1167+98-218+00	1,393.6					EACH
	MEDIAN LT. STA. 1172+80.81-214+49.20	529.9				MILAN BELTWAY	
	MEDIAN RT. STA. 1172+80.81-214+49.20	537.7				LT. STA. 364+11.13-364+24.38	1
	LT. STA. 1173+66.2-218+00	807.9				RT. STA. 356+83.28-356+96.53	1
						JOHN DEERE ROAD	
	VALLEY VIEW					RT. STA. 381+36.31-381+49.56	1
	NW RADIUS STA. 151+15-152+45	207.4				52ND AVENUE	
	SE RADIUS STA. 151+63-154+00	230.3				LT. STA. 1157+96.71-1158+09.96	1
	LT. STA. 152+46.9-154+00	163.2				RT. STA. 1160+35.08-1160+48.33	1
	RT. STA. 152+46.54-154+00	142.6				TOTAL	5
	LT. STA. 159+99.77-160+09.77	10.0					
	TRINITY DRIVE						
	W. RADIUS LT. STA. 0+45-0+98.5	97.6					
	E. RADIUS RT. STA. 0+49-0+98.4	97.6					
	TOTAL	9,997.1					
60605400	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.24 (SPECIAL)	FT.		60618300	CONCRETE MEDIAN SURFACE, 4 INCH	S. F.	
	VALLEY VIEW				BLACKHAWK ROAD		
	RT. STA. 154+00-160+09.8	608.8			N. W. ISLAND LT. STA. 1151+80	75	
					MEDIAN STA. 1152+61.00-1156+63.48	4,687	
	TOTAL	608.8			N. W. ISLAND LT. STA. 1156+58	190	
					S. W. ISLAND RT. STA. 1156+24	1,032	
					52ND AVENUE		
					MEDIAN STA. 1161+66.12-1165+07.35	3,554	
					S. E. ISLAND RT. STA. 1166+53	148	
					N. W. ISLAND LT. STA. 1172+27	134	
					MEDIAN STA. 1172+91.64-214+35.08	5,800	
					44TH STREET		
					LT. STA. 15+53.2-19+56	414.0	
					RT. STA. 15+54.3-16+61.4	111.5	
					RT. STA. 17+92.6-19+69	288.0	
					S. E. ISLAND @ BLACKHAWK RD.	44.9	
					LT. STA. 17+18.70-17+43	36.0	
					TOTAL	1,192.9	
					60619100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	S. F.
						BLACKHAWK ROAD	
						LT. STA. 1148+44.00-1151+63.02	1,908.7
						52ND AVENUE	
						RT. STA. 1157+57.52-1157+90.86	391.2
						RT. STA. 1160+52.50-1161+66.12	979.3
						RT. STA. 1166+44.97-LT. STA. 1171-96.23	2,829.8
						TOTAL	6,109.0
					60624600	CORRUGATED MEDIAN	S. F.
						52ND AVENUE	
						RT. STA. 1165+15.69-1165+53.18	194.9
						LT. STA. 213+89.96-215+70.33	678.5
						TOTAL	873.4
					60900140	TYPE B INLET BOX, STANDARD 609006	EACH
						52ND AVENUE	
						LT. STA. 1157+93.5	1
						TOTAL	1