

EARTHWORK SCHEDULES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	59
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 6"
	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
MILAN BELTWAY STAGE 1					
LT & RT STA. 357+13.69 - 364+16.44	2,748	2,061	48	2,013	289
TOTAL:	2,748	2,061	48	2,013	289

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 6"
	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
JOHN DEERE ROAD STAGE 1					
LT & RT STA. 381+57.89 - 404+00	8,989	6,742	37,093	-30,351	17,825
JOHN DEERE ROAD STAGE 2 PHASE 1					
LT & RT STA. 403+50 - 415+45	4,014	3,011	7,104	-4,094	4,907
LT STA. 409+00 - 418+00	198	149	0	149	4,907
JOHN DEERE ROAD STAGE 2 PHASE 2					
LT STA. 409+00 - 417+10	3,030	2,273	0	2,273	0
JOHN DEERE ROAD STAGE 2 PHASE 3					
LT STA. 409+00 - 417+10	1,403	1,052	375	677	3,712
TOTAL:	17,634	13,226	44,572	-31,347	31,351

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE, 6"
	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
BLACKHAWK ROAD STAGE 2 PHASE 1					
LT & RT STA. 1146+00 - 1152+81	433	325	4,181	-3,856	2,581
BLACKHAWK ROAD STAGE 2 PHASE 2					
LT & RT STA. 1146+00 - 1150+74	423	317	4	313	0
BLACKHAWK ROAD STAGE 2 PHASE 3					
LT & RT STA. 1146+00 - 1152+50	1,019	764	183	581	1,095
BLACKHAWK ROAD STAGE 2 PHASE 4					
LT & RT STA. 1146+00 - 1150+00	79	59	143	-84	607
52nd AVENUE STAGE 1					
LT & RT STA. 1152+81 - 1170+50	1,782	1,337	118,144	-116,808	23,774
52ND AVE DRAINAGE DITCH STA. 46+00 - 48+00	584	438	105	333	1,150
52nd AVENUE STAGE 1 PHASE 1					
LT & RT STA. 1170+50 - 218+50	2,766	2,075	2,900	-826	4,842
TOTAL:	7,086	5,315	125,660	-120,346	34,049