

EARTHWORK SCHEDULES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	61
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
44TH ST. CONNECTOR STAGE 1 PHASE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 0+50 - 8+00	1,495	1,121	899	222	1,570
TOTAL:	1,495	1,121	899	222	1,570

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
VALLEY VIEW STAGE 2 PHASE 3	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 152+50 - 171+29.12	12,438	9,329	3,573	5,756	15,219
TOTAL:	12,438	9,329	3,573	5,756	15,219

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
OLD BLACKHAWK ROAD STAGE 2 PHASE 3	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 0+15 - 1+85	783	587	45	542	458
TOTAL:	783	587	45	542	458

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
TRINITY DRIVE STAGE 1 PHASE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 0+50 - 2+82.82	1,278	959	68	891	808
TOTAL:	1,278	959	68	891	808

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
THIRD STREET STAGE 1 PHASE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 1+30 - 11+50	3,002	2,252	5,094	-2,843	6,977
THIRD STREET STAGE 1 PHASE 2					
LT & RT STA. 0+37 BK. - 1+30	736	552	0	552	143
TOTAL:	3,738	2,804	5,094	-2,291	7,120

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
WETLAND AREAS	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
RAMP 4 INFIELD AREA	25,122	18,842	0	18,842	17,843
TOTAL:	25,122	18,842	0	18,842	17,843
GRAND TOTAL:	82,287	61,715	241,390	-179,675	151,106