

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6194 (109)R, RS-4		KANKAKEE	82	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

66402

TEMPORARY PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION				
EAST DETOUR					
1428	62+00.00 TO 76+94.50	LT	EDGE LINE	WHITE	
2856	62+00.00 TO 76+94.50	LT	CENTERLINE	YELLOW	
1428	62+00.00 TO 76+94.50	RT/LT	EDGE LINE	WHITE	
WEST DETOUR					
1580	98+37.01 TO 113+25.00	RT/LT	EDGE LINE	WHITE	
3160	98+37.01 TO 113+25.00	RT	CENTERLINE	YELLOW	
1580	98+37.01 TO 113+25.00	RT	EDGE LINE	WHITE	
12032	TOTAL				

THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS

SQ FT	LOCATION	
46.8	78+85.00 TO 78+85.00	LEFT-TURN LANE
46.8	TOTAL	

THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION				
ILLINOIS ROUTE 113					
260	33+00 TO 35+60	RT	CENTERLINE	SINGLE YELLOW	
260	33+00 TO 35+60	LT	EDGE LINE	WHITE	
260	33+00 TO 35+60	RT	EDGE LINE	WHITE	
1320	35+60 TO 48+80	LT	EDGE LINE	WHITE	
1320	35+60 TO 48+80	RT	EDGE LINE	WHITE	
792	48+80 TO 56+72	LT	CENTERLINE	SINGLE YELLOW	
792	48+80 TO 56+72	LT	EDGE LINE	WHITE	
792	48+80 TO 56+72	RT	EDGE LINE	WHITE	
1056	56+72 TO 62+00	CL	CENTERLINE	DOUBLE YELLOW	
528	56+72 TO 62+00	LT	EDGE LINE	WHITE	
528	56+72 TO 62+00	RT	EDGE LINE	WHITE	
1970	62+00 TO 71+85	CL	CENTERLINE	DOUBLE YELLOW	
1467	62+00 TO 76+67	LT	EDGE LINE	WHITE	
4600	62+00 TO 108+00	RT	EDGE LINE	WHITE	
600	71+85 TO 74+85	LT	TURN-LANE	DOUBLE YELLOW	
600	71+85 TO 74+85	RT	TURN-LANE	DOUBLE YELLOW	
360	74+85 TO 76+85	RT/LT	TURN-LANE	DOUBLE YELLOW	
760	74+85 TO 78+65	LT	TURN-LANE	DOUBLE YELLOW	
722	79+74 TO 83+35	LT	MEDIAN	DOUBLE YELLOW	
722	79+74 TO 83+35	RT	MEDIAN	DOUBLE YELLOW	
2796	80+04 TO 108+00	LT	EDGE LINE	WHITE	
4930	83+35 TO 108+00	CL	CENTERLINE	DOUBLE YELLOW	
440	108+00 TO 110+20	CL	CENTERLINE	DOUBLE YELLOW	
220	108+00 TO 110+20	LT	EDGE LINE	WHITE	
220	108+00 TO 110+20	RT	EDGE LINE	WHITE	
TOWER ROAD					
1136	3+96.28 TO 9+64.36	CL	CENTERLINE	WHITE	
MAIN STREET					
94	310+08 TO 310+55	CL	CENTERLINE	WHITE	
29545	TOTAL				

THERMOPLASTIC PAVEMENT MARKING - LINE 6"

FOOT	LOCATION				
65	33+00 TO 35+60	CL	SKIP-DASH	YELLOW	
330	35+60 TO 48+80	CL	SKIP-DASH	YELLOW	
198	48+80 TO 56+72	CL	SKIP-DASH	YELLOW	
593	TOTAL				

THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION				
45	74+85 TO 76+85	RT	SKIP-DASH	WHITE	
200	76+85 TO 78+65	RT	LANE LINE	WHITE	
130	78+30.38 TO 78+90.45	LT	ISLAND	WHITE	
375	TOTAL				

THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION				
110	71+85 TO 76+85	LT/RT	MEDIAN DIAGONALS	YELLOW	
53	78+30.38 TO 78+90.45	LT	ISLAND DIAGONALS	WHITE	
88	79+74.69 TO 83+35	LT/RT	MEDIAN DIAGONALS	YELLOW	
251	TOTAL				

THERMOPLASTIC PAVEMENT MARKING - LINE 24"

FOOT	LOCATION				
TOWER ROAD					
24	9+58.87	31.15'	RT	STOP BAR	WHITE
15	9+84.36	0'	RT	STOP BAR	WHITE
MAIN STREET					
12	310+55.14	0'	RT	STOP BAR	WHITE
INDIAN TRAIL					
28	10+45.00	7.5'	RT	STOP BAR	WHITE
79	TOTAL				

RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	
ILLINOIS ROUTE 113		
6	33+00.00 TO 35+60.00	DOUBLE TWO-WAY AMBER MARKER
17	35+60.00 TO 48+80.00	TWO-WAY AMBER MARKER
20	48+80.00 TO 56+72.00	DOUBLE TWO-WAY AMBER MARKER
12	56+72.00 TO 62+00.00	DOUBLE TWO-WAY AMBER MARKER
28	62+00.00 TO 71+85.00	TWO-WAY AMBER MARKER
22	71+85.00 TO 76+65.00	ONE-WAY AMBER MARKER
12	76+65.00 TO 78+85.00	TWO-WAY AMBER MARKER
6	76+65.00 TO 78+85.00	ONE-WAY CRYSTAL MARKER
18	79+74.69 TO 83+35.00	ONE-WAY AMBER MARKER
64	83+35.00 TO 108+00.00	TWO-WAY AMBER MARKER
6	108+00.00 TO 110+20.00	DOUBLE TWO-WAY AMBER MARKER
TOWER ROAD		
14	3+96.28 TO 10+00.00	TWO-WAY AMBER MARKER
225	TOTAL	

PRISMATIC CURB REFLECTOR

EACH	LOCATION		
8	78+50 TO 78+90	LT	INTERSECTION ISLAND
8	TOTAL		

GUARDRAIL MARKERS, TYPE A

EACH	LOCATION		
1	60+30	RT	
1	61+10	RT	
1	61+90	RT	
1	62+70	RT	
4	TOTAL		

TERMINAL MARKERS, DIRECT APPLIED

EACH	LOCATION		
1	59+85.00	RT	
1	63+22.50	RT	
2	TOTAL		

GRATING FOR BOX CULVERT 5' X 3'

EACH	LOCATION			
1	62+44	43.5'	LT	
1	62+44	30.5'	RT	
1	104+24	48.6'	RT	
1	104+32	39.6'	LT	
4	TOTAL			

GRATING FOR BOX CULVERT 6' X 3'

EACH	LOCATION			
1	94+41	48.0'	LT	
1	94+41	52.0'	RT	
2	TOTAL			

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAU 6194 (ILLINOIS ROUTE 113)
SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY

*****DATE*****