COUNTY D3 WEED SPRAYING LASALLE

2005-2

GENERAL NOTES:

Plan dimensions and details relative to the existing roadway and structure have been taken from existing plans and are subject to nominal construction variations. It shall be the contractor's responsibility to verify such dimensions and details in the field and to make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The contractor shall be responsible for protecting utility property from construction operations as outlined in Article 107.31 of the Standard Specifications. The "Julie" Number is 1-800-892-0123. A minimum of forty-eight (48) hours advance notice is required.

Where section or subsection monuments are encountered, the engineer shall be notified before such monuments are removed. The contractor shall protect and carefully preserve all monuments until an authorized surveyor or agent has witnessed or otherwise referenced their location. The contractor shall be responsible for having an authorized surveyor reestablish any section or subsection monuments destroyed by his operations.

Any reference to a standard in these plans shall be interpreted to mean the edition as indicated by the subnumber listed on the index of sheets or the copy of the standard included in these plans.

The following rates of application have been used in calculating plan quantities:

Overdrive	4	Onces/Acre
Transline	8	Onces/Acre
Improved Surfactant	1	Pint/Acre
Drift Control Additive	3.2	Ounces/Acre
Prokoz Spi-Max	0.5	Ounces/Acre
Water	40	Gallon/Acre

12-21-04

PREPARED BY:

EXAMINED BY:

ILLINOIS DEPARTMENT OF TRANSPORTATION **GENERAL NOTES** SCALE: VERT, ORAWN BY

DATE

SECTION: D3 WEED SPRAYING 2005-2

COUNTY: LASALLE

ROUTE: 39 & 80