

SUMMARY OF QUANTITIES

F&P ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	71BR	RANDOLPH	3	73
STA.		TO STA.		
CONTRACT NO.: 76125				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X071 -2A	
X6330190	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL	EACH	3	3	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12	12	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	174	174	
20200100	EARTH EXCAVATION	CU YD	700	700	
20201500	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	267	267	
20400800	FURNISHED EXCAVATION	CU YD	915	915	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	146.4	146.4	
25000200	SEEDING, CLASS 2	ACRE	1.01	1.01	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	91	91	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	91	91	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	91	91	
25100105	MULCH, METHOD 1	ACRE	3	3	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	770	770	
28000300	TEMPORARY DITCH CHECKS	EACH	2	2	
28100105	STONE RIPRAP, CLASS A3	SQ YD	31	31	
28100109	STONE RIPRAP, CLASS A5	SQ YD	2327	2327	
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	2327	2327	
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	1106	1106	
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	99	99	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.1	1.1	
40600300	AGGREGATE (PRIME COAT)	TON	6	6	
40600990	TEMPORARY RAMP	SQ YD	75	75	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	24	24	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	266.7	266.7	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	53.3	53.3	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	2942	2942	
44000100	PAVEMENT REMOVAL	SQ YD	346	346	
44004250	PAVED SHOULDER REMOVAL	SQ YD	782	782	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1907	1907	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	75	75	
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	79	79	
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	133	133	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50102500	CONCRETE REMOVAL (SPECIAL)	CU YD	48.8	48.8	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X071 -2A	
50200100	STRUCTURE EXCAVATION	CU YD	377.4	377.4	
50300100	FLOOR DRAINS	EACH	18	18	
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	117.2	117.2	
50300225	CONCRETE STRUCTURES	CU YD	228.4	228.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	233.7	233.7	
50300260	BRIDGE DECK GROOVING	SQ YD	754	754	
50300300	PROTECTIVE COAT	SQ YD	940	940	
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	18	18	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1	
50500505	STUD SHEAR CONNECTORS	EACH	2862	2862	
50800105	REINFORCEMENT BARS	POUND	31790	31790	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	94920	94920	
51500100	NAME PLATES	EACH	1	1	
54215547	METAL END SECTIONS 12"	EACH	2	2	
58700200	BRIDGE SEAT SEALER	SQ FT	763.4	763.4	
60100945	PIPE DRAINS 12"	FOOT	83	83	
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	2	2	
60900515	CONCRETE THRUST BLOCKS	EACH	2	2	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	650	650	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6	6	
63200310	GUARDRAIL REMOVAL	FOOT	1028.8	1028.8	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1	
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	2	2	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	286	286	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8996	8996	

Rev. 2-24-05

* SPECIALTY ITEMS