

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

URBAN TOTAL QUANTITIES	1000-2A	1000-2A	Y031-1F		X020-2A	Y030-1E		
	4 LANE	2 LANE	TRAFFIC SIGNALS	PARKING LANES	BOX CULVERT	HIGHWAY		
	100% STATE	100% STATE	IL 162 @	50% STATE	SN 060-0403	LIGHTING		
			RIGGIN RD.	50% CITY	100% STATE	100% STATE		
		90% STATE/10% CITY	Y025					

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000-2A	1000-2A	Y031-1F		X020-2A	Y030-1E		
X0324748	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 66"	FOOT	126								
X0069132	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90 11.5"	SQ YD	16,377	14,711	1,666						
XX002154	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	4	4							
XX001875	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	6	6							
XX002155	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	17	11	6						
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1490		1490						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	837		837						
20100500	TREE REMOVAL, ACRES	ACRE	1.1		1.1						
20200100	EARTH EXCAVATION	CU YD	44,377	7232	37145						
20800150	TRENCH BACKFILL	CU YD	7721	6856	865						
20900310	POROUS GRANULAR BACKFILL	TON	14					14			
25000110	SEEDING, CLASS 1A	ACRE	3.8	3.4	0.4						
25000200	SEEDING, CLASS 2	ACRE	12.5		12.5						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1465	317	1148						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1465	317	1148						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1465	317	1148						
25100115	MULCH, METHOD 2	ACRE	16.3	3.5	12.8						
25100630	EROSION CONTROL BLANKET	SQ YD	5491	143	5348						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1628	353	1275						
28000300	TEMPORARY DITCH CHECKS	EACH	268	19	249						
28000400	PERIMETER EROSION BARRIER	FOOT	4335	2580	1755						
28000500	INLET AND PIPE PROTECTION	EACH	36	25	11						
28100107	STONE RIPRAP, CLASS A4	SQ YD	25		25						
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	25		25						
30200600	PROCESSING LIME MODIFIED SOIL 12"	SQ YD	24,336	21,659	2,677						
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	3279	1619	1660						
80201500	LIME	TON	467	416	51						
35300705	PORTLAND CEMENT CONCRETE BASE COURSE 12 1/4"	SQ YD	3127	3127							
30201400	WATER	UNIT	366	299	67						
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	261	22	239						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	11.8	13					1.2	
40600300	AGGREGATE (PRIME COAT)	TON	124.6	56.9	62.1					5.6	
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1						
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	231	151	80						
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	104	104							

7/1/2004
 Thursday July 01, 2004 @ 2:22:34 PM
 c:\p\o\meta\ver\95\p\en\019656adgn L141-63

Rev.