

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	I000-2A	I000-2A	Y031-1F		X020-2A	Y030-1E		
CODE NO	ITEM	UNIT		4 LANE	2 LANE	TRAFFIC SIGNALS	PARKING LANES	BOX CULVERT	HIGHWAY		
						IL 162 @	50% STATE	SN 060-0403	LIGHTING		
				100% STATE	100% STATE	RIGGIN RD.	50% CITY	100% STATE	100% STATE		
						90% STATE/10% CITY	Y025				
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1					
89502380	REMOVE EXISTING HANDHOLE	EACH	5			5					
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5			5					
X0321297	REMOVE EXISTING SIGN POST	EACH	1		1						
X0321600	FORM LINER TEXTURED SURFACE	SQ FT	624	624							
* X0321905	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	526	406	120						
* X0321906	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15"	FOOT	45	45							
* X0321907	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	209	176	33						
* X0321909	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24"	FOOT	95	95							
* X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	279	279							
* X0322089	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	216	216							
* X0322090	STORM SEWER (WATER MAIN REQUIREMENTS) 42 INCH	FOOT	146	146							
X0322178	REMOVE EXISTING LIGHT POLE FOUNDATION	EACH	3						3		
* X0322525	STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH	FOOT	48	48							
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	410	380	30						
X0323818	CLEANING AND PAINTING EXPOSED REBAR	SQ FT	225					225			
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	940	940							
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	158	158							
X4066536	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N70	TON	2727		2727						
X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	4555	3372	851	332					
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	1332		1332						
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	5019	4441	465	113					
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	439	439							
X4403300	CONCRETE MEDIAN REMOVAL	SQ FT	213	213							
X5011100	FOUNDATION REMOVAL	EACH	2		2						
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	28	22	6						
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	5	4	1						
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	1		1						

* SPECIALTY ITEMS

Rev.