



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

March 1, 2005

SUBJECT: FAU 2585 (Meacham Road)
Project M-8003(352)
Section 00-00068-01-WR (Schaumburg)
Cook County
Contract No. 83785
Item 81
March 11, 2005 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Check Sheet 22 now required, added special provision Bridge Median Removal, added pay item (Z0047300 Protective Shield) to page 1 of the Schedule of Prices.

Plans – Sheet 6, Summary of Quantities, added pay item (Z0047300 Protective Shield).

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are displayed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Michael L. Hine
Engineer of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger" followed by "P.E." in a smaller font.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

STATE JOB # - C-91-082-04
 PPS NBR - 1-10812-0000

COUNTY NAME	CODE	DIST	SECTION NUMBER	PROJECT NUMBER	ROUTE
COOK	031	01	00-00068-01-WR (SCHAUMBURG)	M-8003/352/000	FAU 2585

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
A2004724	T-GLED TRI-I SM 3	EACH	72.000 X	=	=	=	=
A2005024	T-GYMNOCOLA DIO 3	EACH	6.000 X	=	=	=	=
C2012036	S-VIBURN DEN SYN 3'	EACH	12.000 X	=	=	=	=
D2C04024	E-YUCCA FILAMN 2'C	EACH	37.000 X	=	=	=	=
XX000613	MODULAR BLOC RET WALL	SQ FT	190.000 X	=	=	=	=
XX002161	ABAND EX WATER MAIN	EACH	2.000 X	=	=	=	=
XX002856	RE-OPTIMIZE TR SIG SY	L SUM	1.000 X	=	=	=	=
XX002866	CONC BAR WALL SPL	CU YD	102.000 X	=	=	=	=
XX003170	CALAM A KARL FORESTER	EACH	17.000 X	=	=	=	=
XX003174	RUDBECK F S GOLDSTRUM	EACH	44.000 X	=	=	=	=
XX003209	LOW VOLTAGE WIRE	FOOT	40.000 X	=	=	=	=
XX003240	MISCAN SIN GRAC 2G	EACH	6.000 X	=	=	=	=
XX003338	TEST HOLE	EACH	46.000 X	=	=	=	=
XX003503	FLARED END SEC REM	EACH	4.000 X	=	=	=	=
XX003718	FIELD TRANSMITTER	EACH	1.000 X	=	=	=	=
Z0047300 PROTECTIVE SHIELD			295.000 X				

Added 3-1-05

RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

<u>CHECK SHEET #</u>	<u>PAGE NO.</u>
1 X State Required Contract Provisions All Federal-aid Construction Contracts (Eff. 2-1-69) (Rev. 10-1-83).....	80
2 X Subletting of Contracts (Federal-aid Contracts) (Eff. 1-1-88) (Rev. 5-1-93).....	82
3 X EEO (Eff. 7-21-78) (Rev. 11-18-80).....	83
4 Specific Equal Employment Opportunity Responsibilities NonFederal-aid Contracts (Eff. 3-20-69) (Rev. 1-1-94).....	94
5 Required Provisions - State Contracts (Eff. 4-1-65) (Rev. 4-1-93).....	100
6 Reserved.....	105
7 Asphalt Quantities and Cost Reviews (Eff. 7-1-88).....	106
8 X National Pollutant Discharge Elimination System Permit (Eff. 7-1-94) (Rev. 1-1-03).....	107
9 Haul Road Stream Crossings, Other Temporary Stream Crossings and In-Stream Work Pads (Eff. 1-2-92) (Rev. 1-1-98).....	108
10 Construction Layout Stakes Except for Bridges (Eff. 1-1-99) (Rev. 1-1-02).....	109
11 X Construction Layout Stakes (Eff. 5-1-93) (Rev. 1-1-02).....	112
12 Use of Geotextile Fabric for Railroad Crossing (Eff. 1-1-95) (Rev. 1-1-97).....	115
13 Asphaltic Emulsion Slurry Seal and Fibrated Asphaltic Emulsion Slurry Seal (Eff. 8-1-89) (Rev. 2-1-97)....	117
14 Bituminous Surface Treatments Half-Smart (Eff. 7-1-93) (Rev. 1-1-97).....	123
15 X Quality Control/Quality Assurance of Bituminous Concrete Mixtures (Eff. 1-1-00) (Rev. 3-1-05).....	129
16 Subsealing of Concrete Pavements (Eff. 11-1-84) (Rev. 2-1-95).....	148
17 Bituminous Surface Removal (Cold Milling) (Eff. 11-1-87) (Rev. 10-15-97).....	152
18 Resurfacing of Milled Surfaces (Eff. 10-1-95).....	154
19 PCC Partial Depth Bituminous Patching (Eff. 1-1-98).....	155
20 Patching with Bituminous Overlay Removal (Eff. 10-1-95) (Rev. 7-1-99).....	157
21 Reserved.....	159
22 X Protective Shield System (Eff. 4-1-95) (Rev. 1-1-03).....	160
23 Polymer Concrete (Eff. 8-1-95) (Rev. 3-1-05).....	162
24 Controlled Low-Strength Material (CLSM) (Eff. 1-1-90) (Rev. 3-1-05).....	164
25 X Pipe Underdrains (Eff. 9-9-87) (Rev. 1-1-98).....	169
26 X Guardrail and Barrier Wall Delineation (Eff. 12-15-93) (Rev. 1-1-97).....	170
27 Bicycle Racks (Eff. 4-1-94) (Rev. 1-1-97).....	175
28 Reserved.....	177
29 Reserved.....	178
30 Reserved.....	179
31 X Night Time Inspection of Roadway Lighting (Eff. 5-1-96).....	180
32 Reserved.....	181
33 English Substitution of Metric Bolts (Eff. 7-1-96).....	182
34 English Substitution of Metric Reinforcement Bars (Eff. 4-1-96) (Rev. 1-1-03).....	183
35 Polymer Modified Emulsified Asphalt (Eff. 5-15-89) (Rev. 1-1-04).....	185
36 Corrosion Inhibitor (Eff. 3-1-80) (Rev. 7-1-99).....	187
37 Quality Control of Concrete Mixtures at the Plant-Single A (Eff. 8-1-00) (Rev. 1-1-04).....	188
38 Quality Control of Concrete Mixtures at the Plant-Double A (Eff. 8-1-00) (Rev. 1-1-04).....	194
39 X Quality Control/Quality Assurance of Concrete Mixtures (Eff. 4-1-92) (Rev. 3-1-05).....	202
40 X Traffic Barrier Terminal Type 1, Special (Eff. 8-1-94) (Rev. 1-1-03).....	215
41 Reserved.....	216
42 X Segregation Control of Bituminous Concrete (Eff. 7-15-97).....	217
43 Reserved.....	220

*Added
3-1-05*

RECURRING LOCAL ROADS AND STREETS SPECIAL PROVISIONS

<u>CHECK SHEET #</u>	<u>Page No.</u>
LRS 1 <input checked="" type="checkbox"/> Cooperation With Utilities (Eff. 1-1-99) (Rev. 1-1-02).....	222
LRS 2 <input checked="" type="checkbox"/> Furnished Excavation (Eff. 1-1-99) (Rev. 1-1-02).....	224
LRS 3 <input checked="" type="checkbox"/> Construction Zone Traffic Control (Eff. 1-1-99).....	225
LRS 4 <input checked="" type="checkbox"/> Flaggers in Work Zones (Eff. 1-1-99).....	226
LRS 5 <input type="checkbox"/> Reserved.....	227
LRS 6 <input type="checkbox"/> Bidding Requirements and Conditions for Contract Proposals (Eff. 1-1-02).....	228
LRS 7 <input type="checkbox"/> Bidding Requirements and Conditions for Material Proposals (Eff. 1-1-03).....	234
LRS 8 <input type="checkbox"/> Failure to Complete the Work on Time (Eff. 1-1-99).....	240
LRS 9 <input type="checkbox"/> Bituminous Surface Treatments (Eff. 1-1-99).....	241
LRS 10 <input type="checkbox"/> Reflective Sheeting Type C (Eff. 1-1-99) (Rev. 1-1-02).....	242
LRS 11 <input type="checkbox"/> Employment Practices (Eff. 1-1-99).....	243
LRS 12 <input type="checkbox"/> Wages of Employees on Public Works (Eff. 1-1-99).....	245
LRS 13 <input type="checkbox"/> Selection of Labor (Eff. 1-1-99).....	246

Storm Sewers (Water Main Requirements)	32
Temporary Ditch Checks.....	32
Temporary Fencing	33
Temporary Information Signing	33
Temporary Pavement Removal.....	34
Terminal Marker - Direct Applied.....	34
Storm Water Pollution Prevention Plan	35

Added
3-1-05

Bridge Median Removal 231

Added
3-1-05

BRIDGE MEDIAN REMOVAL

This work shall conform to Section 440 of the "Standard Specifications" and to **Protective Shield System**, listed as # 22 on the checklist of "Recurring Special Provisions".

This item shall include providing a Protective Shield System between the approximate limits, as follows or by limits identified by the Engineer:

Length - Approximately 136ft from Station 284+38 (Pier #1) to Station 285+70 (Pier #3)
Width - Approximately 20ft centered about the existing open joint on the median.

This item also includes removal of the bridge median as shown on the plans or by limits identified by the Engineer. Disposal of the median material shall be the same as the disposal of the material associated with the existing concrete pavement, with said disposal being incidental to this item.

Basis of Payment.

Removal of the Bridge Median will be paid for at the contract unit price per square foot for **MEDIAN REMOVAL**, which price shall include all labor, material, disposal and equipment necessary to complete the specified work.

The Protective Shield System will be paid for at the contract unit price per square yard for **PROTECTIVE SHIELD**, which price shall include all labor, material, disposal and equipment necessary to complete the specified work.