F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70X) N & TS-1	LASALLE	460	213
STA. ———		TO STA. ———		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 86603

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STANDARDS

000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-02	TEMPORARY EROSION CONTROL SYSTEMS
406201	MAILBOX TURNOUT
420001-05	PAVEMENT JOINTS
420106-02	36' JOINTED PCC PAVEMENT
420111-01	PCC PAVEMENT ROUNDOUTS
442201-01	CLASS C AND D PATCHES
483001-01	PCC SHOULDER
542301	PRECAST REINFORCED CONCRETE FLARED END SECTION
542311	GRATING FOR CONCRETE FLARED END SECTION (FOR 24" THRU 54" PIPE)
602301	INLET - TYPE A
602306	INLET - TYPE B
602401	MANHOLE TYPE A
602406-01	MANHOLE TYPE A, 72" DIAMETER
602601	PRECAST REINFORCED CONCRETE FLAT SLAB TOP
602701	CAST IRON STEPS
604001-02	FRAME AND LIDS TYPE 1
604006-02	FRAME AND GRATE TYPE 3
604036-01	GRATE TYPE 8
604066-01	FRAME AND LID TYPE 15
606001-02	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
665001-01	WOVEN WIRE FENCE
667101	PERMANENT SURVEY MARKERS
701201-01	LANE CLOSURE, 2L, 2W DAY ONLY ON-RD TO 24" OFF-RD FOR SPEEDS > 45 MPH
701301-01	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS - DAY ONLY FOR SPEEDS > 45 MPH
701311-02	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
701321-07	LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
701326-01	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING FOR SPEEDS ≥ 45 MPH
701336-03	LANE CLOSURE, 2L, 2W, WORK ACCESS IN SERIES FOR SPEEDS ≥ 45 MPH
701501-02	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701606-03	URBAN LANE CLOSURE, MULTILANE 2W WITH MOUNTABLE MEDIAN
701701-03	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-03	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
702001-04	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
720006	SIGN PANEL ERECTION DETAILS
720016-01	MAST ARM MOUNTED STREET NAME SIGNS
729001	APPLICATION OF TYPES A AND B METAL POSTS (FOR SIGNS & MARKERS)
780001-01	TYPICAL PAVEMENT MARKINGS
781001-02	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
805001	ELECTRICAL SERVICE INSTALLATION DETAILS
814001	CONCRETE HANDHOLES
814006	DOUBLE HANDHOLES
857001	STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
877001-01	STEEL MAST ARM ASSEMBLY AND POLE
878001-02	CONCRETE FOUNDATION DETAILS
880006	TRAFFIC SIGNAL MOUNTING DETAILS
886001	DETECTOR LOOP INSTALLATIONS
886006	TYPICAL LAYOUTS FOR DETECTION LOOPS

COMMITMENTS

1. ENVIRONMENTAL COORDINATION.

2. DURING NEGOTIATIONS THE FOLLOWING COMMITMENTS WERE MADE TO THE OWNERS OF THE PROPERTY LOCATED BETWEEN STATION 256+49.56 AND 258+04.74 LT.:

   - THE DRIVEWAY SHOULD BE CONSTRUCTED IN SUCH A WAY THE LOW POINT OF THE DRIVEWAY WILL NE LOCATED ABOVE THE FLOW LINE OF THE DITCH.

   - THE PROPERTY OWNERS POINTED OUT THAT THERE IS AN EXISTING FIELD TILE WHICH TIES INTO THE EXISTING STORM SEWER AT APPROXIMATELY STATION 256+56 LT. IT IS UNKNOWN WHAT ELSE MAY BE TIED INTO THE FIELD TILE, A COMMITMENT WAS MADE TO CONSTRUCT A CONFLICT MANHOLE IF THE FIELD TILE CONFLICTS WITH THE PROPOSED STORM SEWER.

   - IN ADDITION TO THESE COMMITMENTS, THE PROPERTY OWNERS POINTED OUT THAT THERE IS AN EXISTING TWO INCH (2") PLASTIC WATER LINE APPROXIMATELY STATION 257+00 LT. AND A SANITARY SERVICE LINE TEN FEET (10') NORTH OF THE WATER LINE WITHIN THE CONSTRUCTION LIMITS.

3. DURING NEGOTIATIONS, A COMMITMENT WAS MADE TO CONTACT THE OWNER OF THE PROPERTY FROM STATION 252+64.93 AND 254+09.34 LT. PRIOR TO ENTRANCE RECONSTRUCTION TO DETERMINE IF STAGED CONSTRUCTION SHOULD BE UTILIZED ON THEIR ENTRANCE. (SEE COMMITMENT FILE FOR NAME AND PHONE NUMBER.)

4. DURING NEGOTIATIONS, A COMMITMENT WAS MADE TO THE OWNERS OF THE PROPERTY FROM STATION 260+04.11 TO 261+93.91 LT. THAT THE BRICK PILLARS ADJACENT TO THE ENTRANCE WILL NOT BE DISTURBED.

5. DURING NEGOTIATIONS, A COMMITMENT WAS MADE TO PROVIDE ACCESS AT ALL TIMES TO THE ENTRANCE AT STATION 252+64 LT. BY STAGING THE ENTRANCE CONSTRUCTION.

6. DURING NEGOTIATIONS, A COMMITMENT WAS MADE REGARDING ACCESS TO ST. VINCENT'S CEMETERY. THE ENTRANCE ALONG IL 351 LOCATED AT APPROXIMATELY STATION 258+71 AND THE ENTRANCE ON NORTH 30TH ROAD LOCATED AT APPROXIMATELY STATION 52+30 ARE THE MOST FREQUENTLY USED ENTRANCES FOR FUNERALS AND THEY SHOULD NOT BE CLOSED AT THE SAME TIME

LEGEND

BITUMINOUS SURFACE REMOVAL-BUTT JOINT	
TEMPORARY RAMP	
PAVEMENT REMOVAL	
CONCRETE, SIDEWALK AND CURB AND GUTTER REMOVAL	
BASE COURSE	
BASE COURSE WIDENING	
DRIVEWAY PAVEMENT REMOVAL	
BITUMINOUS DRIVEWAY PAVEMENT	
PCC DRIVEWAY PAVEMENT	
INCIDENTAL BITUMINOUS SURFACING	
AGGREGATE SURFACE COURSE	
RIPRAP	
BITUMINOUS BASE COURSE	
BITUMINOUS CONCRETE BASE COURSE WIDENING	
PAVEMENT PATCH	
CURB AND GUTTER REMOVAL	
CONCRETE MEDIAN SURFACE REMOVAL	
BITUMINOUS SHOULDER REMOVAL	
TREE REMOVAL	

GENERAL INFORMATION	1
DIMENSION INFORMATION	1
CULVERT INFORMATION	1
STORM SEWER INFORMATION	1
HOUSE NUMBER & PARCEL NUMBER	807
CONSTRUCTION LIMITS	
TREE TRUNK PROTECTION	
CATCH BASIN, MANHOLE TO BE REMOVED	R
FUTURE IMPROVEMENT	
UTILITY TO BE ADJUSTED	A
SEEDING, TEMPORARY EROSION CONTROL SEEDING MULCH	
INLET PROTECTION	
PERIMETER EROSION BARRIER	
TO BE RELOCATED	REL
DIRECTION OF TRAFFIC	
TYPE C BIDIRECTIONAL REFLECTOR	
TYPE III BARRICADE W/ FLASHING LIGHTS	
TYPE III BARRICADE	
DRUM OR BARRICADE WITH STEADY BURNING LIGHT	
WORK ZONE	
DRUM OR BARRICADE	

UTILITIES

TELEPHONE: AMERITECH — AT&T
65 WEST WEBSTER ST.
4TH FLOOR
JOLIET, IL 60431
(815) 774-6772

CABLE TV: TCI CABLEVISION OF IL VALLEY
2216 MARQUETTE ROAD
PERU, IL 61354
(815) 223-1106

INSIGHT COMMUNICATIONS
2216 MARQUETTE RD.
PERU, IL 61354

WATER, SANITARY SEWER & STORM SEWER:
CITY OF LASALLE
745 SECOND STREET
LaSALLE, IL 61301
(815) 223-6344

ELECTRICAL & GAS:
ILLINOIS POWER
340 RACCUGLIA DRIVE
P.O. BOX 1428
LASALLE, IL 61301-3428

CONTAMINATION SITE:
EXCAVATION NOT TO EXCEED LISTED DEPTH UNLESS APPROVED BY ENGINEER.

0'
2'
3'
4'
6'

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STANDARDS, UTILITIES & LEGEND

FAU 6108 (IL. RTE. 351)
SECTION (71X) N & TS-1
LASALLE COUNTY

SCALE: VERT. / HORIZ.
DATE 11/20/01

DRAWN BY: MABUS
DESIGNED BY: BOTT
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
(IP SPRINGFIELD)
CONSULTING ENGINEERS
TRANSPORTATION DIVISION
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-000715
(217) 193-8664, 1227 PO. BOX 707, P.O. ENGINEERING CORPORATION
(217) 193-8664, 1227 PO. BOX 707, P.O. E-MAIL: GBINFO@GREENEANDBRADFORD.COM

COMPUTER FILE NO. 01194STAN
PROJECT 01194_B_N
08/05-04-GSJ

IDOTPL-50 1"=50' 8/07/00

FAU 6108 (IL. RTE. 351) LASALLE COUNTY