

CONTRACT NO. 90843

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY STPF TWO-LANE RURAL ROADWAY 80% FEDERAL 20% STATE X081-2A
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	58
542I3447	END SECTIONS 12"	EACH	4
542I3450	END SECTIONS 15"	EACH	4
542I3657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	7
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	289
58700200	BRIDGE SEAT SEALER	SQ FT	735
60100945	PIPE DRAINS 12"	FOOT	171
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	8
60255500	MANHOLES TO BE ADJUSTED	EACH	1
60500060	REMOVING INLETS	EACH	1
60600095	CLASS SICONCRETE (OUTLET)	CU YD	3.2
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	958.0
60614600	PAVED DITCH (SPECIAL)	FOOT	9
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	4
60900515	CONCRETE THRUST BLOCKS	EACH	4
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1712.5
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	8
63200310	GUARDRAIL REMOVAL	FOOT	2627
63300115	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, SINGLE RAIL	FOOT	496
63700600	CONCRETE BARRIER, SINGLE FACE (SPECIAL)	FOOT	65
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106700	TEMPORARY RUMBLE STRIP	EACH	9
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	459
70300200	TEMPORARY PAVEMENT MARKING	FOOT	5925
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2128
70400100	TEMPORARY CONCRETE BARRIER	FOOT	970
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	890
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3765
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6
*78200405	GUARDRAIL MARKERS	EACH	29

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY STPF TWO-LANE RURAL ROADWAY 80% FEDERAL 20% STATE X081-2A
*78200500	BARRIER WALL MARKERS	EACH	12
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	19
XX003505	PORTLAND CEMENT CONCRETE SIDEWALK 10 INCH (SPECIAL)	SQ FT	112
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	742
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX 'C', N50	TON	307
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	152
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1
X5020503	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 3	EACH	1
*X7016510	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL) LOCATION 1	EACH	1
*X7016520	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL) LOCATION 2	EACH	1
Z0002600	BAR SPLICERS	EACH	1952
Z0002900	BASE COURSE (OPTION)	SQ YD	1293
*Z0003900	BICYCLE RAILING	FOOT	250
**Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4
**Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4
Z0037300	PAVEMENT GROOVING	SQ YD	500
Z0038700	PERMANENT BENCH MARKS	EACH	2
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	1

* DENOTES SPECIALTY ITEM
** FUND CODE: SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 2 OF 2
DRAWN BY MLO
CHECKED BY SJK
DATE 5/03