

ROUTE NO.	SECTION	COUNTY	SHEET	SHEET
TR 447	*	Vermilion	16	3
FED. ROAD DIST. NO. 7		ALLOCATION	FED. AID PROJECT	
*00-03128-00-BR				

SEEDING, CLASS 2	
LOCATION	ACRE
STA 105+00 TO STA 109+85	0.41
STA 110+15 TO STA 113+04.43	0.25
TOTAL	0.66

MULCH, METHOD 2	
LOCATION	ACRE
STA 105+00 TO STA 109+85	0.41
STA 110+15 TO STA 113+04.43	0.25
TOTAL	0.66

TREE REMOVAL	
LOCATION	ACRE
RT. STA. 105+00 TO STA. 106+50	0.01
RT. STA. 106+50 TO STA. 109+70	0.22
RT. STA. 110+00 TO STA. 111+80	0.12
RT. STA. 111+80 TO STA. 113+04.43	0.03
LT. STA. 110+20 TO STA. 111+50	0.08
LT. STA. 111+50 TO STA. 112+70	0.03
TOTAL	0.49

CONSTRUCTION LAYOUT	
LOCATION	L SUM
SEC. 00-03128-00-BR	1
TOTAL	1

PIPE CULVERTS, TYPE 1 ALUMINIZED CORRUGATED STEEL PIPE, 18" DIA	
LOCATION	FOOT
LT STA 107+49	40
RT STA 106+61	48
RT STA 111+60	40
TOTAL	128

PIPE CULVERT REMOVAL	
LOCATION	FOOT
RT STA 107+49	27
TOTAL	27

AGGREGATE BASE COURSE, TYPE A, 8"		
LOCATION	WIDTH (FT)	SQ. YD.
STA 105+00 TO STA 108+58.51	12'-6" TO 20'-0"	611
STA 110+33.43 TO STA 113+04.43	11'-6" TO 20'-0"	475
TOTAL		1086

AGGREGATE SURFACE COURSE, TYPE B	
LOCATION	TON
RT STA 106+61	19
LT STA 107+49	19
RT STA 111+60	19
TOTAL	57

BITUMINOUS RESURFACING SCHEDULE									
STATION TO STATION	LENGTH (FT)	BIT. CONC. SURF. CSE. SUPERPAVE MIX "C," N50 (TON)			BIT. CONC. BINDER CSE. SUPERPAVE MIX C, IL-19.0, N50 (TON)			BITUMINOUS MATERIALS PRIME COAT (GALLON)	AGGREGATE PRIME COAT (TON)
		WIDTH (FT)	AREA (SQ FT)	QUANTITY (TON)	WIDTH (FT)	AREA (SQ FT)	QUANTITY (TON)	QUANTITY (GALLON)	QUANTITY (TON)
STA 105+00 TO STA 108+38.51	338.51	12.5 to 20.0	5,501	52	12.5 to 20.0		52	245	1.0
STA 108+38.51 TO STA 110+33.43	194.92	27.0	5,263	113					
STA 110+33.43 TO STA 113+04.43	271.00	20.0 to 11.5	4,269	40	20.0 to 11.5		40	190	0.7
TOTAL				205			92	435	1.7

DSGN	K.E. Brandau				
DR	R.T. Mumm				
CHK	K.E. Brandau				
APVD	K.E. Brandau	NO.	DATE	REVISION	BY

FRAUENHÖFFER

Frauenhoffer and Associates, P.C. Consulting Engineers
3002 Crossing Court Champaign, IL 61822 217-351-6268

SCHEDULE OF QUANTITIES

CARROLL ROAD DISTRICT
SECTION 00-03128-00-BR
VERMILION COUNTY

SHEET	3
DWG NO.	sched.dgn
DATE	APR 2004
PROJ NO.	3080