

ROUTE NO.	SECTION	COU	NTY	TOTAL SHEETS	SHEET NO.	SHEET	NO. 2
F.A.P. RTE. 774	1Ø7BY	EFFIN	igham	344	312	29 SH	EETS
FED, ROAD D	IST. NO. 7	ILLINOIS	FED, AID	PROJECT-			

NO. 20

CONTRACT NO. 94827

NOTES

Hatched areas indicate Concrete Removal. Existing reinforcement not extending into areas of new construction shall be cut at the removal line and removed. Exposed portion will be covered with a layer of epoxy. Cost included with Concrete Removal.

Existing reinforcement extending into the removal area are to be cleaned, straightened and incorporated into the new construction. All reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete . Removal.

Cross hatched areas indicate Slopewall Removal.

BILL OF MATERIAL

Item	Unit	Quantity	
Concrete Removal	Cu. Yd.	29.3	
Slopewall Removal	Sq. Yd.	321	

SHEET TITLE	
EAST ABUTMENT CONCRETE REM	OVAL
PROJECT IL RTE. 32/33 OVER LITTLE WABASH RIVER F.A.P. RTE. 774 SECTION 107BY EFFINGHAM COUNTY STATION 1011+50.17 STRUCTURE NO. 025-0078	PRUJECT NO. O2017 SCALE DATE DRAWN BY TFG CNECKED BY GJB/MCB
COOMBE-BLOXDORF P.C. Engineers /Land Surveyors Springfield, Illinois Design Firm License No. 184-002703	DRAWING ND. 20 DF 29 SHTS