

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

District 6
Schedule of Overhead Sign Structure Repair & Replacement

Location No.:	1	State I.D. No.:	6S084I055L082.1				
County:	SANGAMON	Route:	I-55	M.P.:	82.1	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	116.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE-SPAN	EACH	2.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	372.00					
REMOVE & REINSTALL WALKWAY	FOOT	57.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	24.60					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
IMPACT ATTENUATOR REMOVAL	EACH	1.00					
SIGN PANEL - TYPE 3	SQ YD	402.00					
STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FT POSTS	FOOT	137.50					
TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.00					
TRAFFIC BARRIER TERMINAL, TYPE 1 SPL (TANGENT)	EACH	1.00					
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, (TANGENT)	EACH	1.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
CONSTRUCTION LAYOUT	L SUM	0.14					
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.14					
MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	3.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
This structure is being completely replaced.							

Location No.:	2	State I.D. No.:	6S054I155L001.9				
County:	LOGAN	Route:	I-155	M.P.:	1.9	Direction:	SB
Description of Work	Unit	Quantity					
RELOCATE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE-SPAN	EACH	2.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	542.00					
REMOVE & REINSTALL WALKWAY	FOOT	34.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	8.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.20					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	75.00					
SIGN PANEL - TYPE 3	SQ YD	540.00					
REMOVE REERECT TRAFFIC BARRIER TERMINAL, T 2	EACH	1.00					
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, (TANGENT)	EACH	1.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
CONSTRUCTION LAYOUT	L SUM	0.14					
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.14					
MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	2.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
The end supports and foundations are being replaced.							

Location No.:	3	State I.D. No.:	6S054I055L128.2				
County:	LOGAN	Route:	I-55	M.P.:	128.2	Direction:	SB
Description of Work	Unit	Quantity					
RELOCATE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE-SPAN	EACH	2.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	469.00					
REMOVE & REINSTALL WALKWAY	FOOT	34.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	9.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	31.20					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	75.00					
SIGN PANEL - TYPE 3	SQ YD	405.00					
REMOVE REERECT TRAFFIC BARRIER TERMINAL, T 2	EACH	1.00					
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, (TANGENT)	EACH	1.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
CONSTRUCTION LAYOUT	L SUM	0.14					
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.14					
MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	2.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
The end supports and foundations are being replaced.							

Location No.:	4	State I.D. No.:	6C084I072R103.0				
County:	SANGAMON	Route:	I-72	M.P.:	103	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A	FOOT	30.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE-CANT	EACH	1.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	84.00					
REMOVE & REINSTALL WALKWAY	FOOT	17.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	7.30					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
SIGN PANEL - TYPE 3	SQ YD	102.00					
STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	112.50					
REMOVE REERECT TRAFFIC BARRIER TERMINAL, T 2	EACH	1.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
CONSTRUCTION LAYOUT	L SUM	0.14					
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.14					
MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	3.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
This structure is being completely replaced.							

Location No.:	5	State I.D. No.:	6C084I055R101.8				
County:	SANGAMON	Route:	I-55	M.P.:	101.8	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A	FOOT	30.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE-CANT	EACH	1.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	84.00					
REMOVE & REINSTALL WALKWAY	FOOT	17.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	7.10					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	25.00					
TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.00					
SIGN PANEL - TYPE 3	SQ YD	84.00					
TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 2	EACH	1.00					
REMOVAL AND REPLACEMENT OF STEEL PLATE BEAM GUARDRAIL, RAIL ELEMENT	FOOT	100.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
CONSTRUCTION LAYOUT	L SUM	0.14					
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.14					
MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	3.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
This structure is being completely replaced.							

Location No.:	6	State I.D. No.:	6S084I055L094.7				
County:	SANGAMON	Route:	I-55	M.P.:	94.7	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	111.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE-SPAN	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	364.00					
REMOVE & REINSTALL WALKWAY	FOOT	54.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	24.10					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	37.50					
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, (TANGENT)	EACH	1.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
CONSTRUCTION LAYOUT	L SUM	0.14					
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.14					
MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
This structure is being completely replaced.							

FILE NAME *	USER NAME *	DESIGNED - ---	REVISED - ---
		CHECKED - ---	REVISED - ---
PLOT SCALE *		DRAWN - ---	REVISED - ---
PLOT DATE *		CHECKED - ---	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Various	D-6 OVD SIN STR REPL II-II	Logan/Sangamon	29	4
CONTRACT NO. 46134			ILLINOIS FED. AID PROJECT	