

 \sim

When cantilever forming brackets are used, the work shall be done according to Article 503.06(b) of the Standard Specifications, except as modified below and in the details shown on this sheet. The finishing machine rails shall be placed on the top flange of the exterior beams.

The beams or girders, supporting cantilever forming brackets, shall be tied together at 4 foot intervals.

For Standard construction, or Stage Construction the Hardwood bracing materials shall be placed as shown between webs of beams in each bay.

OR SUPERSTRUCTURES WITH	F.A.P. RTE,	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
STRUCTURE NO. 056–0277	324	24B-2	MCHENRY	76	52
		D-91-178-09	CONTRACT	NO. 6	OF64
SHEETS	ILLINOIS FED. AID PROJECT				