

SHEET NO. 1 OF 1 SHEET

GENERAL NOTES

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

Existing pavement markings shall be temporarily covered prior to application of the Concrete Sealer, to prevent the material from being applied to the markings. The temporary covering shall be removed after application of the Concrete Sealer and prior to opening to traffic. Cost is included with "Concrete Sealer".

See special provisions for lane closure requirements. Roadway shall only be opened to traffic after sealant has completely cured.

SCOPE OF WORK

Apply Concrete Sealer to top of deck surface and top and inside vertical face of parapets.

TOTAL BILL OF MATERIAL

| Item | Unit | Total | |
|-----------------|---------|-------|--|
| Concrete Sealer | Sq. Ft. | 34007 | |
| | | | |

r ∉ FAI Rte. 55



| | <u>GENERAL PLAN AND ELEVATION</u> E.B. 1-55 OVER BNSF RAILWAY YARD TRACK FAI RTE 55 SECTION (0102-631,ETC,0507-635K)RS-3 COOK COUNTY STRUCTURE NO. 016-0004 | | | | | | | |
|-------|--|---------------------------|------------------------------|----------|-------|-------|--|--|
| : | | | | | | | | |
| ATION | | F.A.I. RTE. | SECTION | COUNTY | TOTAL | SHEET | | |
| 04 | | 55 | (0102-631,ETC,0507-635K)RS-3 | СООК | 197 | 53 | | |
| ~ 1 | | | | CONTRACT | NO. | 60164 | | |
| | | ILLINOIS FED. AID PROJECT | | | | | | |
| | | | | | | | | |