



The Contractor shall use 5/8" diameter epoxy grouted anchors according to the Standard Specification 584.

All steel rail elements shall be galvanized according to Article 509.05 of the Standard Specifications.

BILL OF MATERIAL

Item	Unit	Total Quantity	Loc. 2
Bridge Fence Railing (Sidewalk)	Foot	140	140

7-1-10 (10'-0" Maximum Post Spacing)

FILE NAME =	USER NAME = gorengoutab	DESIGNED -	REVISED -
c:\pwwork\pwwork\gorengoutab\d0208706	D164110-shr-plen.dgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8" = 1' IN.	CHECKED -	REVISED -
	PLOT DATE = 12/8/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BRIDGE FENCE RAILING, SIDEWALK MOUNTED (MODIFIED)
STRUCTURE NO. 022-0036

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	2010-123-1	DUPAGE	11	9
CONTRACT NO. 60M60			ILLINOIS FED. AID PROJECT	