




## PLAN







SECTION B-B
(At East Abutment)

SCALE:

## BILL OF MATERIAL

ITEM	UNIT	TOTAL
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	- 4
Deck Slab Repair (Full Depth, Type II)	Sq. Yd.	19
Deck Slab Repair (Partial)	Sq. Yd.	20
Silicone Joint Sealer, 1 3/4"	Foot	45
Silicone Joint Sealer, 2 1/2"	Foot	45

## LEGEND:

Deck S.

Deck Slab Repair (Partial)



Deck Slab Repair (Full Depth, Type I)



Deck Slab Repair (Full Depth, Type II)

## Notes:

- 1. See General Note 4 on Sheet S1 of S6.
- 2. Removal and disposal of the existing joint fillers will be included with the cost of Silicone Joint Sealer, of the size specified.
- 3. Existing plates to be cleaned prior to installation of backer rod. Cost included with Silicone Joint Sealer, of the size specified.



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DECK AND EXPANSION JOINT REPAIRS
WESTBOUND 1-80 OVER MIDLAND AVENUE
SN 099-0051

SHEET S3 OF S6 STA. TO STA.

L SECTION COUNTY TOTAL SHEET NO. 0 99 (4&4-1) RS-3 WILL 203 95 CONTRACT NO. 60M66

\\fs1\tranprojects\udot\21050.005 (1-80 phase :1)\drawings\cadd sheets\bridge p&e\midland\wb\699-0051-D160M68-Deck-Midland.dgn