

	DESIGNED - DF	REVISED -			TEMPORARY CONCRETE BARRIER FOR
USER NAME = Imueller	DRAWN - LAM	REVISED -	HBP	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	WESTBOUND FAI-80 OVER CENTER
PLOT SCALE = NTS	CHECKED - BLU	REVISED -	a Illinois Partners		STRUCTURE NO. 099-
PLOT DATE = 1/19/2011 2:17:55 PM	DATE - 1/20/2011	REVISED -			SHEET NO. S- 5 OF S- 5 S
S#\1056B\05_CADD\CADD Sheets\0990054-60M66-005-	TCB.dgn				

<u>NOTES</u>

 Drill 1<sup>1</sup><sub>4</sub>" φ Holes through new overlay into slab for 1" φ x 13" dowel bars. Traffic side only as directed by Engineer. Repair hole with non-shrink epoxy grout as directed by Engineer. Cost of anchorage and repair included with Temporary Concrete Barrier.

STAGE CONSTRUCTION	F.A.I RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
R STREET RAMP CC	80	99(4&4-1)RS-3	WILL	203	109
-0054			CONTRACT	NO. 60	)M66
SHEETS		DAD DIST. NO. ILLINOIS FED. A			