



BILL OF MATERIAL

ITEM					UNIT	TOTAL							
Structural F	Repair	Of	Concrete	(Depth	Equal	To	0r	Less	Than	5	Inches)	Sq.Ft.	<i>1</i> 5

LEGEND:

Spalled or unsound concrete

Areas of proposed pier repairs are estimated. Actual type, location and dimensions of pier repairs are to be determined by the Engineer during construction.

	DESIGNED - PCA	REVISED -	
USER NAME = Isupencheck	DRAWN - LK	REVISED -	
PLOT SCALE = 1:1	CHECKED ~ MEA	REVISED -	
PLOT DATE = 19-JAN-2011	DATE - 1/21/2011	REVISED -	
FILE NAME = IP_PWP:dms34565\0990	Ø61-6ØM66-ØØ8-PIER.DGN		



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WESTBOUND	PIER 1 REPAIRS	F.A.I. RTE.	
	FAI-80 OVER RAILROAD/GARDNER STREET STRUCTURE NO. 099-0061	80	
	SHEET NO. S-8 OF 14 SHEETS	FED. R	OAI

COUNTY TOTAL SHEET NO.
WILL 203 159
CONTRACT NO. 60M66 SECTION 99 (4&4-1) RS-3 FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT