
## **GENERAL NOTES**

- 1. Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.
- 2. Reinforcement bars designated (E) shall be epoxy coated
- 3. Protective coat shall not be applied to surfaces to which Waterproofing Membrane System is applied.
- 4. A cantilevered sheet piling does not appear feasible and additional members or other retention systems may be necessary. The Contractor shall submit a temporary soil retention system design including plan details and calculations for review and acceptance by the Engineer.


## TOTAL BILL OF MATERIAL

	ltem .	Unit	Total
*	Porous Granular Embankment, Special	Cu. Yd.	1,190
	Structural Excavation	Cu. Yd.	4,536
	Concrete Structures	Cu. Yd.	683.6
	Rubbed Finish	Sq. Ft.	5, <i>1</i> 50
*	Formliner Textured Surface	Sq. Ft.	2,470
	Reinforcement Bars, Epoxy Coated	Pound	96,970
	Bar Splicers	Each	128
	Name Plates	Each	1
	Membrane Waterproofing	Sq. Ft.	2,813
	Geocomposite Wall Drain	Sq. Yd.	669
*	Pipe Underdrains for Structures, 6"	Foot	410
*	Temporary Soil Retention System	Sq. Ft.	2,207
*	Ornamental Railing	Foot	<i>1</i> 45
*	Staining Concrete Structures	Sq. Yd.	275

\* See Special Provisions




## TEMPORARY SOIL RETENTION SYSTEM - PLAN



TEMPORARY SOIL RETENTION SYSTEM - ELEVATION




450 E Devon Ave, Suite 300 Itasca, Illinois 60143 Tel: 630.773.3900 Fax: 630.773.3975



3602

08-F3000-07-BT



SECTION II CONSTRUCTION

(Looking North)

S2 of S11

TOTAL SHEETS

LAKE

SHEET NO.

LAKE COUNTY FOREST PRESERVE DISTRICT REVISIONS GENERAL NOTES, TOTAL BILL OF NAME DATE MATERIAL & STAGING DETAILS GILMER ROAD TRAIL UNDERPASS SEC 08-F3000-07-BT STA. 274+14.15 STRUCTURE NO. 049-NO06 DRAWN BY: D. Atkins

CHECKED BY: G. Hatlestad DATE: December 17, 2010