

Symmetrical about © Bridge

Ties at 4'-0" cts.
Finishing machine rail

Hardwood 4" x 4" blocks
at 4'-0" cts.

STAGE CONSTRUCTION

FORM BRACES FOR STANDARD CONSTRUCTION

CANTILEVER FORMING BRACKETS
FOR SUPERSTRUCTURES WITH
W27 BEAMS AND SMALLER
STRUCTURE NO. 045-3020

WILLS BURKE KELSEY ASSOCIATES LTD.

116 West Main Street, Suite 201
St. Charles, Illinois 60174
(630) 443-7755

SHEET NO.20

F.A.U. SECTION COUNTY TOTAL SHEETS NO. 2332 03-14185-02-BR KANE 73 44

CONTRACT NO. 63521

FED. ROAD DIST. NO. | ILLINOIS | FED. AID | PROJECT

 DESIGNED - AEU

 CHECKED - DLS

 DRAWN - AWH

 CHECKED - AEU

PLOT CREATION DATE = 10/19/2010

as modified below and in the details shown on this sheet.
The finishing machine rails shall be placed on the top flange of the exterior beams.
The beams or girders, supporting cantilever forming brackets, shall be fied together at 4 foot intervals.

When cantilever forming brackets are used, the work shall be done according to Article 503.06(b) of the Standard Specifications, except

For Standard construction, or Stage Construction the Hardwood bracing materials shall be placed as shown between webs of beams in each bay.