


PAY ITEM	UNIT	QUANTITY
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH	1
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	419
PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6
PEDESTRIAN PUSH-BUTTON	EACH	6
MODIFY EXISTING CONTROLLER CABINET	EACH	1
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
FIBER OPTIC PATCH PANEL	EACH	1
INTERSECTION VIDEO TRAFFIC MONITORING SYSTEM WITH PTZ CAMERA	EACH	1
UNINTERRUPTIBLE POWER SUPPLY (SPECIAL KDOT)	EACH	1
OUTDOOR RATED NETWORK CABLE	FOOT	130
MANAGED ETHERNET SWITCH, TYPE 1	EACH	1
MALFUNCTION MANAGEMENT UNIT	EACH	1
VIDEO VEHICLE DETECTION IP INTERFACE PANEL UPGRADE	EACH	1



SCALE: NONE

 \sim

CONSTRUCTION NOTES:

- 1 CONTRACTOR TO INSTALL NEW PEDESTRIAN PUSH-BUTTON
- (2) CONTRACTOR TO REMOVE EXISTING PEDESTRIAN PUSH-BUTTON AND INSTALL NEW PEDESTRIAN PUSH-BUTTON WITH PEDESTRIAN PUSH-BUTTON SIGNS. USE EXISTING ELECTRIC CABLE.

(2) (2) (3) (4) (4)		COUNTY
	DIVISION OF	TRANSPORTATION

USER NAME = JM	DESIGNED	-	DG	REVISED -
	DRAWN	-	JM/SM	REVISED -
PLOT SCALE = 1' = 20'	CHECKED	-	DG '	REVISED -
PLOT DATE = 12-21-2010	DATE	-	12-21-2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CABLE	PLAN	AND	PHASE DE	SIGNATION	DIAGRAM
	ş				
 SHEET	NO.	OF	SHEETS	STA.	TO STA.

F.A.P SECTION COUNTY TOTAL SHEETS NO.

336 09-00272-01-TL KANE 68 **9**CONTRACT NO. 63540