

SPACER BAND

SPACER BAND

SPACER BAND

CASING PIPE

SECTION

B"-9" TOPSOIL

B"-9" TOPSOIL

GRANULAR TRENCH BACKFILL CA-6
SHALL BE PROVIDED FOR PIPPS
BENEATH OR WITHIN 3' OF
EXISTING OR PROPOSED PAVEMENTS,
DRIVEWAYS, OR SIDEWALKS.

BEDDING (SEE NOTES 2 & 3)

IF ENCOUNTERED, REMOVE
UNSUITABLE MATERIAL,
AS DIRECTED BY THE ENGINEER


-BITUMINOUS SURFACE


NOTES:

1. TRENCH SHALL BE IN ACCORDANCE WITH OSHA SAFETY STANDARDS.

- 2. BEDDING SHALL BE REQUIRED TO BE A MINIMUM THICKNESS EQUAL TO 1/4 OF THE OUTSIDE DIAMETER OF THE PIPE BUT SHALL NOT BE LESS THAN 4". AS A MINIMUM, BEDDING AND HAUNCHING MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION." THE GRADATIONS SHALL EITHER BE FA-1 OR FA-2.
- 3. WHEN STORM SEWER CONSTRUCTION OCCURS IN COMBINED SEWER AREAS, BEDDING AND HAUNCHING MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF THE "METROPOLITAN WATER RECLAMATION DISTRICT OF GREATER CHICAGO." THE GRADATIONS SHALL EITHER BE CA-11 OR CA-13.

## TRENCH BACKFILL DETAIL FOR STORM SEWER





CROSS SECTION
WATER MAIN CROSSING

FILE NAME = 09858-DTLS-01 - IDOT P01	USER NAME =	DESIGNED — PKB	REVIȘED —		/ /1SI SIREEI			F.A.U.	SECTION	COUNTY	TOTAL S	SHEET
		CHECKED — PKB REVISED — STATE (		STATE OF ILLINOIS	F ILLINOIS	<b>_</b>		1537	06-00050-00-GS	соок	209	69
	PLOT SCALE =	DRAWN — PS	REVISED	DEPARTMENT OF TRANSPORTATION	CONSTRUCTION DETAILS			CONTRA		NO. 63556	3	
	PLOT DATE = 12/23/10	CHECKED AG	REVISED —		SCALE:	SHEET NO. 69 OF 209 SHEETS STA.	TO STA.	FED. ROAD D	DIST. NO. 1 ILLINOIS FED. A	ID PROJECT CRE-	-9003(709)	