### 100% STATE QQ14

## MCHD CLAIM NO. 751531 KNOX COUNTY

# **COMMITMENTS**

No commitments have been made for this project.

## **GENERAL NOTES**

Plan dimensions and details relative to existing plans are subject to routine variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished based upon the unit price bid for the work.

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60 (IL Modified). See Special Provisions

Reinforcement bars designated (E) shall be epoxy coated. The Contractor will submit to the Engineer a satisfactory progress schedule and critical path schedule which shall show the proposed sequence of work at the time of the pre-construction conference.

		KNUX COUNTY			
CODE NO.	ITEM	UNIT	URBAN	TOTAL	
50102400	CONCRETE REMOVAL	CUYD	2	2	
50300255	CONCRETE SUPERSTRUCTURE	CUYD	2	2	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	10,930	10,930	
67100100	MOBILIZATION	LSUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	LSUM	1	1	
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	LSUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	F00T	2600	2600	
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SOFT	867	867	
X7010216	TRAFFIC CONTROL AND PROTECTION. (SPECIAL)	LSUM	1	1	
X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1	
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	10,040	10,040	
Z0003600	BEAM STRAIGHTENING	LSUM	1	1	
<i>20073300</i>	TEMPORARY SHORING AND CRIBBING	LSUM	1	1	
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	LSUM	1	. 1	
			***************************************		

SN.048-0065 FARNHAM ST. OVER US34

FILE NAME =	USER NAME = jonesce	DESIGNED - CEJ	REVISED		GENERAL NOTES & COMMITMENTS	F.A.P. SECTION	COUNTY TOTAL SHEET
SNØ48-0065 FarnhamStovrUS34.dgn		DRAWN ~ CEJ	REVISED	STATE OF ILLINOIS	SUMMARY OF QUANTITIES	29 (21-HB-2)I-5	KNOX 14 2
	PLOT SCALE = 103.7051 ' / IN.	CHECKED	REVISED	DEPARTMENT OF TRANSPORTATION		STEEL BEAM REPAIRS	CONTRACT NO. 68A08
	PLOT DATE = 12/23/2010	DATE - 12/17/2010	REVISED - 12/23/2010		SCALE: SHEET NO OF SHEETS   STA TO STA	FEO. ROAD DIST. NO. 4 ILLINOIS FED. A	ND PROJECT