

LOCATION OF WORK:

CULVERT NO. 1

CULVERT NO. 2

STA. 172+31

STA. 272+92

RURAL

RURAL

S.N. 092-8086

S.N. 092-8087

PROP PCBC

PROP PCBC

10 X 5

7 X 5

80% FED

80% FED

20% STATE

20% STATE

0040

0040

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
20200100	EARTH EXCAVATION	CU YD	183.0	50.0	133.0
20400800	FURNISHED EXCAVATION	CU YD	92.0	26.0	66.0
20700220	POROUS GRANULAR EMBANKMENT	CU YD	374.0	165.0	209.0
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	730.0	400.0	330.0
* 25000200	SEEDING, CLASS 2	ACRE	1.0	0.4	0.6
* 25000350	SEEDING, CLASS 7	ACRE	1.0	0.4	0.6
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90.0	36.0	54.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90.0	36.0	54.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90.0	36.0	54.0
* 25100115	MULCH, METHOD 2	ACRE	1.0	0.4	0.6
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100.0	40.0	60.0
28000305	TEMPORARY DITCH CHECKS	FOOT	260.0	80.0	180.0
28000400	PERIMETER EROSION BARRIER	FOOT	1,196.0	397.0	799.0
28100101	STONE RIPRAP, CLASS A1	SQ YD	374.0	252.0	122.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	213.0	213.0	
28200200	FILTER FABRIC	SQ YD	213.0	213.0	
44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	235.0	125.0	110.0
44213100	PAVEMENT FABRIC	SQ YD	235.0	125.0	110.0
44213204	TIE BARS 3/4"	EACH	36.0	17.0	19.0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	351.0	173.0	178.0

* SPECIALTY ITEMS

CONTINUED NEXT SHEET

FILE NAME =	USER NAME = sherer_jm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\pwidot\sherer_jm\d0189007\0570617-sht-500.dgn	DRAWN - JMS	REVISED -	711					115CR	VERMILION	39	4	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. TO STA.					CONTRACT NO. 70617				
PLOT DATE = 11/16/2010	DATE - 031210	REVISED -	ILLINOIS FED. AID PROJECT									