

VERMILION COUNTY STRUCTURES ACTUAL MEASUREMENTS

VERMILION COUNTY STRUCTURES SCHEDULE OF QUANTITIES																			
			RAILROAD COORDINATION							TRAFFIC CONTROL & PROTECTION				PROSECUTION & PROGRESS		RURAL	URBAN		
SN	ROUTE CARRIED	FEATURE CROSSED	OWNER	DOT/AAR NO.	MILE POST	FLAGGER REQUIRED	RRPLI REQUIRED	STANDARD 701400	STANDARD 701406	STANDARD 701411 (DL ONLY)	STANDARD 701446	LOCATION	SUMMARY	CHANGEABLE MESSAGE SIGN (Calendar Days)	ESTIMATED WORKING DAYS			PROSECUTION	
092-0003	I-74 (EB)	MIDDLEFORK VERM RIV						1	1	1		4	4-701400 SET-UPS (2 DL; 2 PL)	2-CMS (1EB; 1-WB); 7 CALENDAR DAYS PRIOR; 8 WORKING DAYS; 15 DAYS EACH DIRECTION; TOTAL 30 CALENDAR DAYS; 18 VERMILION COUNTY STRUCTURES ON FAI 74	2	1 DAY DRIVING LANES WB & EB; 1 DAY PASSING LANES WB & EB	X		
092-0004	I-74 (WB)	MIDDLEFORK VERM RIV					1	1	1				4-701406 SET-UPS (2 DL; 2 PL)				X		
092-0006	I-74 (EB)	SALT FORK VERM RIVER					1	1	1				4-701411 SET-UPS (2 EB; 2 WB)					X	
092-0007	I-74 (WB)	SALT FORK VERM RIVER					1	1	1				2-WD'S (1DL; 1PL); 4 STRUCT.					X	
092-0008	I-74 (EB)	N&S & FAU 7026(L ST)	NSRR	479 871 J	304.45	YES	YES	1	1			3	4-701400 SET-UPS (2 DL; 2 PL) 4-701406 SET-UPS (2 DL; 2 PL) 4-701411 SET-UPS (2 EB; 2 WB) 2-WD'S (1DL; 1PL); 6 STRUCT.		2	1 DAY DRIVING LANES WB & EB; 1 DAY PASSING LANES WB & EB		X	
092-0009	I-74 (WB)	N&S & FAU 7026(L ST)	NSRR	479 871 J	304.45	YES	YES	1	1								4-701400 SET-UPS (2 DL; 2 PL)		X
092-0010	I-74 (EB)	"G" ST(FAU 7026)						INCL.	INCL.	1							4-701406 SET-UPS (2 DL; 2 PL)		X
092-0011	I-74 (WB)	"G" ST(FAU 7026)						INCL.	INCL.	1							4-701411 SET-UPS (2 EB; 2 WB)		X
092-0012	I-74 (WB)	CNRL & FR1563 & 1611	CSX	542 383 B	125.45	YES	YES	1	1	1							2-WD'S (1DL; 1PL); 6 STRUCT.		X
092-0013	I-74 (EB)	CNRL & FR1563 & 1611	CSX	542 383 B	125.45	YES	YES	1	1	1									X
092-0014	I-74 (WB)	VERMILION RIVER						1	1	1		2	4-701400 SET-UPS (2 DL; 2 PL) 4-701406 SET-UPS (2 DL; 2 PL) 4-701411 SET-UPS (2 EB; 2 WB) 2-WD'S (1DL; 1PL); 4 STRUCT.		2	1 DAY DRIVING LANES WB & EB; 1 DAY PASSING LANES WB & EB		X	
092-0015	I-74 (EB)	VERMILION RIVER						1	1	1							4-701400 SET-UPS (2 DL; 2 PL)		X
092-0018	I-74 (EB)	STONY CREEK						1	1	1							4-701406 SET-UPS (2 DL; 2 PL)		X
092-0019	I-74 (WB)	STONY CREEK						1	1	1							4-701411 SET-UPS (2 EB; 2 WB)		X
092-0023	I-74(WB)&RAMP	CSX RR & MS 9010	CSX	353 719 Y	127.76	YES	YES	1	1	1		1	4-701400 SET-UPS (2 DL; 2 PL) 4-701406 SET-UPS (2 DL; 2 PL) 3-701411 SET-UPS (1EB; 2 WB) 2-WD'S (1DL; 1PL); 4 STRUCT.		2	1 DAY DRIVING LANES WB & EB; 1 DAY PASSING LANES WB & EB		X	
092-0024	I-74(EB)	CSX RR & MS 9010	CSX	353 719 Y	127.76	YES	YES	1	1	1							4-701400 SET-UPS (2 DL; 2 PL)		X
092-0025	I-74 (WB)	RAMP 22.31						1	1	1				4-701406 SET-UPS (2 DL; 2 PL)				X	
092-0026	I-74 & RAMP	RAMPS 21.94/22.31						1	1	1				3-701411 SET-UPS (1EB; 2 WB)				X	
TOTAL TC&P SET-UPS; LOCATIONS; CMS CALENDAR DAYS; ESTIMATED WORKING DAYS:								16	16	15	0	4	30	8					

*FY2011 BRIDGE DECK SEALING
**CHAMPAIGN, MCLEAN & VERMILION

FILE NAME =	USER NAME = ceorlockjd	DESIGNED - TJB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	VERMILION COUNTY STRUCTURES TRAFFIC CONTROL & PROTECTION	F.A.I. RTE.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\p\dot\ceorlockjd\0185207\09	70861-sht-schedule.dgn	DRAWN - BBP	REVISED -			74	*	**	19	19	
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 70861					
	PLOT DATE = 11/15/2010	DATE - 09/20/10	REVISED -			SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	